

Section

Letter of Transmittal

Figures and Tables

Executive Summary

Introduction

Problem

Site Condition

Topography

Utility Conflicts

Right-of-Way and Easements

Watershed Hydrology

General Design Criteria

Hydraulic Analysis

Inlet Spillway

Outlet works

Appendix A

HEC-1 Output (Pre-Project)

HEC-1 Output (Post Project with Outlet Works)

HEC-1 Output (Post Project w/o Outlet Works)

Appendix B

HECRAS Output – Inlet Channel

Appendix C

Spillway Design Calculations

Appendix D

SECTION **II**
LETTER OF TRANSMITTAL **II**
FIGURES AND TABLES **II**
INTRODUCTION..... **II**

INTRODUCTION

Tatum Wash is a tributary of Indian Bend Wash (IBW). Tatum Wash begins in the Phoenix Mountain Preserve which is located in north Phoenix between Shea Boulevard and Lincoln Drive and between 40th Street and Tatum Boulevard. The wash collects and conveys flows in a northeasterly direction from the mountain preserves to the IBW. No official floodplain has been delineated, but many homes north of Shea Boulevard have been flooded from relatively low frequency events, events less than the 10- year event.

The City of Phoenix submitted Tatum Wash to the Flood Control District Of Maricopa County for consideration as a flood control project.

PROBLEM

Tatum Wash is a natural wash that begins in the Phoenix Mountain Preserves. The wash is a well-defined channel from its origin to a few hundred feet south of Shea Boulevard. A few hundred feet upstream (south) of Shea Boulevard, the banks of Tatum Wash end and the flows transition from channel flow to sheet flow and spread out onto a vacant lot abutting Shea Boulevard. A single catch basin was placed on the south side of Shea Boulevard with the construction of the Shea Boulevard Storm Drain Project to intercept the 1-yr flows. Flows in excess of the 1-yr event spill onto Shea Boulevard depositing heavy debris that is picked up in the wash's upper reach. In addition to

closing Shea Boulevard, the flows continue overland through a developed residential neighborhood flooding homes and closing streets before it outfalls into the IBW.

The natural wash upstream (south) of Shea Boulevard does not have the capacity to convey the entire 100-year flow event within its banks. A previous analysis of Tatum Wash determined that the wash in its present condition has the capacity to convey approximately 621 cfs without any breakouts. The analysis further determined that minor improvements at various breakout locations could increase its conveyance capacity to 1,000 cfs. For this reason, the inlet spillway for the detention basin was sized to accommodate 1,000 cfs.

UTILITIES

Shea Boulevard has a number of existing utilities located with the road rights-of-way. The outfall for the detention basin must cross three existing utilities before connecting into the existing 78" storm drain line. The three utilities are a 4" gas line, an abandoned 6" water line, and a 15" sewer line. No conflict exists, but the detention basin outfall pipe comes very near to the sewer line as it crosses over it. Because of the close proximity, the existing sewer line will be replaced with ductile iron pipe (DIP). The DIP replacement will serve two purposes: one, it will provide more clearance between the lines because it has a thinner structural section than the vcp pipe that it is replacing; and two, it will be stronger and not susceptible to cracking from trench settlement like the existing vcp pipe would be.

RIGHT-OF-WAY AND EASEMENTS

The limits of the detention basin and the channel inlet improvements fit within existing drainage easements and the single parcel purchased for this project. Tatum Wash is confined within an existing 100-foot easement with manmade banks between 40th Street and the site of the detention basin. Along the each side of the 100-foot easement, there is an additional 15-foot drainage easement recorded and along the parcel's northern boundary for the western portion of the property there is a 5-foot drainage easement. Other non-drainage easements exist on the parcel: there is a 15-foot sewer easement paralleling the parcel's western boundary and a slope easement along the property's northern boundary. The slope easement is no longer needed because the road is at the same grade as the surrounding property and will remain so after construction of the basin.

Hydraulic Analysis

Inlet Spillway

The inlet spillway collects runoff from Tatum Wash and conveys the flows into the sediment/detention basin. The inlet spillway is a baffled chute spillway. The chute blocks within the spillway dissipate the energy of the falling flows before they reach the floor of the basin. This design was selected over constructing an energy dissipator at the end or bottom of the drop to facilitate removing sediment and debris from the floor of the basin. This design also does not rely on tailwater to facilitate energy dissipation.

Tatum Wash inlet channel immediately upstream of the spillway has the capacity to convey the entire 100-year event of 2,315 cfs without overtopping its banks provided that it could make it to the basin. Hydraulic analysis of the existing channel found that the current 100-yr discharge of Tatum is unlikely to make it to the inlet structure because the flows would break-out of the banks upstream of 44th Street and at 44th Street. The existing wash's current capacity is approximately 620 cfs and could be increased to 1,000 cfs with only minor channel improvements to the natural wash. For this reason, the spillway was sized to accommodate flows of 1,000 cfs

Large diameter dumped rip rap is being placed around the inlet spillway in the event that any flows greater than the design amount reach the spillway. The minimum side wall height of the spillway is 4 feet 8 inches which is greater than the depth of flow for a discharge of 2,300 cfs, but the rip rap will protect the structure from splashing which will exceed the minimum wall height for this amount of discharge.

Outlet works

The outlet works consist of a rectangular concrete structure constructed back into the front (north) side slope of the basin. The structure has two ungated orifices in the side and grates at the top to allow flows to be discharged into a 42" pipe which will convey the flows to an existing 78" storm drain in Shea Boulevard. Flap gates or backflow preventers will be placed on the two 24" orifices to prevent flows in the storm drain from entering the sedimentation/detention basin. The elevation of the grated top of

the outlet structure is set one foot below the emergency spillway to capture water in case the openings become clogged.

Through research of the design calculations for the storm drain in Shea Boulevard, it was determined that the storm drain has the capacity to collect 81 cfs from the Tatum Wash. The existing inlet will be removed and a new outlet structure will be built to drain the basin. The outlet was sized to limit the discharges to the 81 cfs when there are flows of 440 cfs in the storm drain. This amount was defined as being the 2-yr return event by the City of Phoenix's Shea Boulevard Drainage Study dated May 1976. To determine the tailwater condition for the outlet structure, the hydraulic gradeline for 520 cfs (440 in the storm darin plus 80 cfs from Tatum Wash) was modeled using Storm Cadd and using the elevations for the storm drain from as-builts for project ST-75091.01 dated 1-18-80 beginning at its outfall, the Indian Bend Wash (IBW). When the storm drain is empty, the outlet structure will be able to pass 151 cfs before flows will begin discharging over the emergency spillway.

	Peak Inflow (cfs)	Peak Discharge to Storm Drain(cfs)	Peak Discharge to Emergency Spillway (cfs)
Pre-Project	2315	80	N/A
Post Phase 1 Project	2315	*151	2164
**Post Phase 2 Project	383	82	0

* Exceeds discharge of 81 cfs; assumption is zero tailwater in Shea Boulevard storm drain.

** Phase 2 – upstream basin in the Phoenix Mountain Preserves containing 145 Ac-Ft of storage

Phase 2 - Mountain Preserve Basin(s)

The sedimentation/detention basin at Shea Boulevard is only the first phase in solving the flooding problems. The basin's size is small and lends itself well to solving the sediment problem caused by runoff from the Phoenix Mountain Preserves, but only provides flood protection from approximately the 2-yr rainfall event. Additional basins placed higher up in the watershed are necessary to provide 100-yr flood protection to the area south of Shea Boulevard.


For the purpose of sizing a future basin(s) upstream in the mountain preserves, Phase 2, the existing HEC-1 model was modified to include 145 Ac-Ft of storage in the mountain preserves. This amount was derived through an iterative process by increasing the amount of storage at a proposed site for a future basin until no flows from the 100-yr event exited the proposed lower detention/sedimentation basin via the emergency spillway. The outlet during this event was assumed to be unclogged and functioning properly limiting discharge to the existing storm drain in Shea Boulevard to 82 cfs (See HEC-1 output file: TTM-100.dat).

More detailed hydraulics will be required when actually sizing a detention basin(s) upstream in the mountain preserves than only providing 145 Ac-Ft of storage. Design parameters for the outlet will include that the outflows do not exceed the capacity of the existing channel for the reach between the mountain preserves (existing capacity is approximately 620 cfs) and the proposed Tatum Wash Detention Basin No. 1, include that the outflows do not exceed the 1,000 cfs capacity of the spillway into Tatum Wash


Detention Basin No. 1, and that the outflows combined with the runoff from the 100-yr event does not cause any flows to exit the detention/sedimentation basin at Shea Boulevard via the emergency spillway.

TATUM WASH DETENTION BASIN NO. 1 DESIGN REPORT

AUGUST, 1997




**FLOOD CONTROL DISTRICT OF MARICOPA COUNTY
ENGINEERING DIVISION
PROJECT No. 580040**



Tatum Wash Detention No. 1

DESIGN REPORT



Property of
Flood Control District of MC Library
Please Return to
2801 W. Durango
Phoenix, AZ 85009




April, 1997

Prepared For:
Flood Control District of Maricopa County
2801 West Durango
Phoenix, Arizona 85009
Michael S. Ellegood, P.E.
Chief Engineer & General Manager

Prepared by:
Engineering Division
Flood Control District of Maricopa County



FCD Project No. 580040



FLOOD CONTROL
DISTRICT OF
MARICOPA COUNTY


**PRELIMINARY DESIGN
SUBMITTAL
TATUM WASH
DETENTION BASIN NO 1**

**PRELIMINARY DESIGN
SUBMITTAL
TATUM WASH
DETENTION BASIN NO 1**

Tatum Wash Detention Basin No. 1

TABLE OF CONTENTS

	Section
HEC1 Models	1
Spillway Design	2
Outfall Sizing	3
Construction Special Provisions	4
Engineer's Cost Estimate (Draft)	5
Preliminary Plans	6



```

*****
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* SEPTEMBER 1990 *
* VERSION 4.0 *
* RUN DATE 07/22/1997 TIME 15:39:24 *
*****

```

```

*****
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*****

```

```

X X XXXXXXX XXXXX X
X X X X X XX
X X X X X X
XXXXXXX XXXX X XXXXX X
X X X X X X
X X X X X X
X X XXXXXXX XXXXX XXX

```

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1GS, HEC1DB, AND HEC1KW.

THE DEFINITIONS OF VARIABLES -RTIMP- AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE. THE DEFINITION OF -AMSKK- ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION

NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE, SINGLE EVENT DAMAGE CALCULATION, DSS:WRITE STAGE FREQUENCY, DSS:READ TIME SERIES AT DESIRED CALCULATION INTERVAL LOSS RATE:GREEN AND AMPT INFILTRATION KINEMATIC WAVE: NEW FINITE DIFFERENCE ALGORITHM

1 HEC-1 INPUT PAGE 1

```

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10
1 ID TATUM WASH PROJECT SUB-AREAS 1 AND 2 COMBINED - 2/9/95
2 ID 100YR-6HR STORM = 3.20" ASSUMED NORMAL CONDITION W/ DTHETA=0.250
3 ID STORM SIZE = 2.28 SQ. MI (TOTAL AREA)
4 ID HYDROGRAPH PLOT FOR 5 DETENTION BASIN SITES (*.DSS)
5 ID DETENTION BASIN A LOCATED SOUTH OF SHEA BLVD
6 ID SPILLWAY IS OVER THE S/W INTO THE ROAD
7 ID LOW FLOW OUTLET INCLUDED FOR TATUM BASIN
8 ID NO BASIN SIZING SHOWN IN THE PHX MTN PRESERVES
9 ID FILE:TMM-NOW.DAT
*DIAGRAM
10 IT 2 1JAN96 0001 2000
11 IO 5
12 KK SIB
13 KM SUB-BASIN SIB
14 KM 6-HOUR RAINFALL, PATTERN NO. 1.88 WAS USED TO FIND TC & R FOR THIS BASIN
15 KM THIS BASIN USED RAINFALL REDUCTION FACTOR OF .978
16 KO 5
17 BA .230
18 IN 15
19 KM RAINFALL DEPTH OF 3.20 WAS SPACIALLY REDUCED AS SHOWN BY THE PB RECORD
20 PB 3.131
21 KM THE FOLLOWING PC RECORD USED A 6-HOUR STORM WITH A PATTERN No. OF 1.88
22 PC .000 .009 .016 .025 .034 .042 .051 .059 .067 .076
23 PC .087 .100 .120 .160 .248 .442 .711 .846 .904 .939
24 PC .951 .964 .976 .988 1.000
25 LG .200 .250 4.300 .500 35.000
26 UC .363 .185
27 UA 0 3 5 8 12 20 43 75 90 96
28 UA 100
29 KK RSIB
30 KM ROUTING THROUGH SIC
31 KO 5
32 RS 3 FLOW -1
33 RC .035 .035 .035 2138 .028
34 RX 0 36 66 90 126 150 168 228
35 RY 7 7 7 0 0 4 6 22
36 KK SIA
37 KM SUB-BASIN SIA
38 KO 5
39 BA .330
40 LG .200 .250 4.300 .500 35.000
41 UC .363 .185
42 UA 0 3 5 8 12 20 43 75 90 96
43 UA 100
44 KK RSLA
45 KM ROUTING THROUGH SIC
46 KO 5
47 RS 3 FLOW -1
48 RC .035 .035 .035 2025 .030
49 RX 0 0.5 1 126 136 251 252 253
50 RY 5 5 5 0 0 5 5 5

```

PAGE 2

```

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10
51 KK SIC
52 KM SUB-BASIN SIC
53 KO 5
54 BA .110
55 LG .200 .250 4.300 .500 35.000
56 UC .329 .265
57 UA 0 3 5 8 12 20 43 75 90 96
58 UA 100
59 KK CPIC

```



```

184      .          S2C
      .          .
192      CP2C.....
      V
      V
196      RCF2C
      .
      .
202      .          S2D
      .          .
210      .          .          S2I
      .          .          .
218      CP2DI.....
      V
      V
221      RCFDI
      .
      .
227      .          S2E
      .          .
235      CP2E.....
      V
      V
238      BSN-A
      .
251      -----> DVRTI
247      SPILLI

```

(***) RUNOFF ALSO COMPUTED AT THIS LOCATION

```

*****
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* SEPTEMBER 1990 *
* VERSION 4.0 *
* RUN DATE 07/22/1997 TIME 15:39:24 *
*****

```

```

*****
* U.S. ARMY CORP'S OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*****

```

TATUM WASH PROJECT SUB-AREAS 1 AND 2 COMBINED - 2/9/95
100YR-6HR STORM = 3.20". ASSUMED NORMAL CONDITION W/ DTHETA=0.250
STORM SIZE = 2.28 SQ. MI (TOTAL AREA)
HYDROGRAPH PLOT FOR 5 DETENTION BASIN SITES (*.DSS)
DETENTION BASIN A LOCATED SOUTH OF SHEA BLVD
SPILLWAY IS OVER THE S/W INTO THE ROAD
LOW FLOW OUTLET INCLUDED FOR TATUM BASIN
NO BASIN SIZING SHOWN IN THE PHX MTN PRESERVES
FILE:TMM-NOW.DAT

*** ERROR *** SPECIFIED START AND END DATES RESULT IN TOO MANY TIME PERIODS

```

11 IO      OUTPUT CONTROL VARIABLES
          IPRNT      5  PRINT CONTROL
          IPLOT      0  PLOT CONTROL
          QSCAL      0.  HYDROGRAPH PLOT SCALE

IT         HYDROGRAPH TIME DATA
          NMIN       2  MINUTES IN COMPUTATION INTERVAL
          IDATE      1JAN96  STARTING DATE
          ITIME      0001  STARTING TIME
          NQ         300  NUMBER OF HYDROGRAPH ORDINATES
          NDDATE     1JAN96  ENDING DATE
          NDTIME     0959  ENDING TIME
          ICENT      19  CENTURY MARK

```

```

COMPUTATION INTERVAL .03 HOURS
TOTAL TIME BASE      9.97 HOURS

```

```

ENGLISH UNITS
DRAINAGE AREA      SQUARE MILES
PRECIPITATION DEPTH  INCHES
LENGTH, ELEVATION  FEET
FLOW               CUBIC FEET PER SECOND
STORAGE VOLUME     ACRE-FEET
SURFACE AREA       ACRES
TEMPERATURE        DEGREES FAHRENHEIT

```

```

16 KO      OUTPUT CONTROL VARIABLES
          IPRNT      5  PRINT CONTROL
          IPLOT      0  PLOT CONTROL
          QSCAL      0.  HYDROGRAPH PLOT SCALE

31 KO      OUTPUT CONTROL VARIABLES
          IPRNT      5  PRINT CONTROL
          IPLOT      0  PLOT CONTROL
          QSCAL      0.  HYDROGRAPH PLOT SCALE

38 KO      OUTPUT CONTROL VARIABLES
          IPRNT      5  PRINT CONTROL
          IPLOT      0  PLOT CONTROL
          QSCAL      0.  HYDROGRAPH PLOT SCALE


46 KO      OUTPUT CONTROL VARIABLES
          IPRNT      5  PRINT CONTROL
          IPLOT      0  PLOT CONTROL
          QSCAL      0.  HYDROGRAPH PLOT SCALE

53 KO      OUTPUT CONTROL VARIABLES
          IPRNT      5  PRINT CONTROL

```

233	UA	0	5	16	30	65	77	84	90	94	97
234	UA	100									
235	KK	CP2E									
236	KM	AT SHEA BLVD. POTENTIAL DETENTION BASIN SITE 5									
237	HC	2									
238	KK	BSN-A									
239	KO	2	0								
240	ZW	A=TATUM	B=INFLOW	C=FLOW	E=2MIN	F=WO					
241	KM	DETENTION BASIN LOCATED ON THE SOUTH SIDE OF SHEA BLVD									
242	ZW	A=TATUM	B=CUTFLOW	C=STAGE	E=2MIN	F=WO					
243	RS	1	STOR	-1							
244	SV	0	3.13	7.63	12.51	17.80	23.49	29.61	32.83	36.16	36.16
245	SQ	0	0	21	30	57	72	83	151	395	1061
246	SE	1380.5	1382	1384	1386	1388	1390	1392	1393	1394	1395
247	KK	SPILL1									
248	KM	ACTUAL LOW FLOWS GO TO SHEA STORM DRAIN									
249	KM	DIVERSION BASED UPON STAGED OUTLET									
250	KM	LOW FLOW WILL BE CONSIDERED FOR SIZING UPPER BASIN									
251	DT	DVRT1									
252	DI	0	50	83	395	2400					
253	DQ	0	50	83	151	151					
254	ZZ										

SCHEMATIC DIAGRAM OF STREAM NETWORK



```

        IPLOT      0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE
62 KO   OUTPUT CONTROL VARIABLES
        IFRNT     5 PRINT CONTROL
        IPLOT     0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE
66 KO   OUTPUT CONTROL VARIABLES
        IFRNT     5 PRINT CONTROL
        IPLOT     0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE
73 KO   OUTPUT CONTROL VARIABLES
        IFRNT     5 PRINT CONTROL
        IPLOT     0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE
81 KO   OUTPUT CONTROL VARIABLES
        IFRNT     5 PRINT CONTROL
        IPLOT     0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE
88 KO   OUTPUT CONTROL VARIABLES
        IFRNT     5 PRINT CONTROL
        IPLOT     0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE
97 KO   OUTPUT CONTROL VARIABLES
        IFRNT     5 PRINT CONTROL
        IPLOT     0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE
101 KO  OUTPUT CONTROL VARIABLES
        IFRNT     5 PRINT CONTROL
        IPLOT     0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE
108 KO  OUTPUT CONTROL VARIABLES
        IFRNT     5 PRINT CONTROL
        IPLOT     0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE
116 KO  OUTPUT CONTROL VARIABLES
        IFRNT     5 PRINT CONTROL
        IPLOT     0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE

```

```

*****
*           *
*   PARK   *
*           *
*****

```

```

119 KO  OUTPUT CONTROL VARIABLES
        IFRNT     3 PRINT CONTROL
        IPLOT     0 PLOT CONTROL
        QSCAL     0. HYDROGRAPH PLOT SCALE
        CITY OF PHX EQUESTRIAN PARK IN MTN PRESERVES
        PROPOSED FUTURE PHASE OF TATUM WASH PROJECT
        NOT USED FOR THIS RUN TO DETERMINE PHASE 1 CONDITION

```

```

DT      DIVERSION
        ISTD      DIV1  DIVERSION HYDROGRAPH IDENTIFICATION
DI      INFLOW      .00 10000.00
DQ      DIVERTED FLOW .00 .00

```

PEAK FLOW		TIME	DIVERSION HYDROGRAPH DIV1			
(CFS)	(HR)	(CFS)	6-HR	24-HR	72-HR	9.97-HR
+	0.	.03	0.	0.	0.	0.
		(INCHES)	.000	.000	.000	.000
		(AC-FT)	0.	0.	0.	0.
CUMULATIVE AREA =			1.77 SQ MI			

PEAK FLOW		TIME	HYDROGRAPH AT STATION PARK			
(CFS)	(HR)	(CFS)	6-HR	24-HR	72-HR	9.97-HR
+	2212.	4.33	337.	204.	204.	204.
		(INCHES)	1.772	1.783	1.783	1.783
		(AC-FT)	167.	168.	168.	168.
CUMULATIVE AREA =			1.77 SQ MI			

```

127 KO  OUTPUT CONTROL VARIABLES
        IFRNT     5 PRINT CONTROL

```


244 SV	STORAGE	.0	3.1	7.6	12.5	17.8	23.5	29.6	32.8	36.2	36.2
245 SQ	DISCHARGE	0.	0.	21.	30.	57.	72.	83.	151.	395.	1061.
246 SE	ELEVATION	1380.50	1382.00	1384.00	1386.00	1388.00	1390.00	1392.00	1393.00	1394.00	1395.00

HYDROGRAPH AT STATION BSN-A

DA	MON	HRMN	ORD	OUTFLOW	STORAGE	STAGE	DA	MON	HRMN	ORD	OUTFLOW	STORAGE	STAGE	DA	MON	HRMN	ORD	OUTFLOW	STORAGE	STAGE
1	JAN	0001	1	0.	3.1	1382.0	1	JAN	0321	101	22.	8.0	1384.2	1	JAN	0641	201	69.	37.4	1394.9
1	JAN	0003	2	0.	3.1	1382.0	1	JAN	0323	102	22.	8.1	1384.2	1	JAN	0643	202	68.	37.4	1394.9
1	JAN	0005	3	0.	3.1	1382.0	1	JAN	0325	103	22.	8.2	1384.2	1	JAN	0645	203	66.	37.4	1394.9
1	JAN	0007	4	0.	3.1	1382.0	1	JAN	0327	104	22.	8.3	1384.3	1	JAN	0647	204	64.	37.4	1394.9
1	JAN	0009	5	0.	3.1	1382.0	1	JAN	0329	105	22.	8.4	1384.3	1	JAN	0649	205	62.	37.4	1394.9
1	JAN	0011	6	0.	3.1	1382.0	1	JAN	0331	106	23.	8.5	1384.4	1	JAN	0651	206	61.	37.4	1394.9
1	JAN	0013	7	0.	3.1	1382.0	1	JAN	0333	107	23.	8.6	1384.4	1	JAN	0653	207	59.	37.4	1394.9
1	JAN	0015	8	0.	3.1	1382.0	1	JAN	0335	108	23.	8.8	1384.5	1	JAN	0655	208	57.	37.4	1394.9
1	JAN	0017	9	0.	3.1	1382.0	1	JAN	0337	109	23.	8.9	1384.5	1	JAN	0657	209	55.	37.4	1394.9
1	JAN	0019	10	0.	3.1	1382.0	1	JAN	0339	110	24.	9.0	1384.6	1	JAN	0659	210	53.	37.4	1394.9
1	JAN	0021	11	0.	3.1	1382.0	1	JAN	0341	111	24.	9.2	1384.6	1	JAN	0701	211	51.	37.4	1394.9
1	JAN	0023	12	0.	3.1	1382.0	1	JAN	0343	112	24.	9.4	1384.7	1	JAN	0703	212	49.	37.4	1394.9
1	JAN	0025	13	0.	3.1	1382.0	1	JAN	0345	113	25.	9.6	1384.8	1	JAN	0705	213	47.	37.4	1394.8
1	JAN	0027	14	0.	3.1	1382.0	1	JAN	0347	114	25.	9.9	1384.9	1	JAN	0707	214	45.	37.4	1394.8
1	JAN	0029	15	0.	3.1	1382.0	1	JAN	0349	115	26.	10.2	1385.0	1	JAN	0709	215	43.	37.4	1394.8
1	JAN	0031	16	0.	3.1	1382.0	1	JAN	0351	116	26.	10.6	1385.2	1	JAN	0711	216	41.	37.4	1394.8
1	JAN	0033	17	0.	3.1	1382.0	1	JAN	0353	117	27.	11.0	1385.4	1	JAN	0713	217	39.	37.4	1394.8
1	JAN	0035	18	0.	3.1	1382.0	1	JAN	0355	118	28.	11.6	1385.6	1	JAN	0715	218	38.	37.4	1394.8
1	JAN	0037	19	0.	3.1	1382.0	1	JAN	0357	119	30.	12.3	1385.9	1	JAN	0717	219	36.	37.4	1394.8
1	JAN	0039	20	0.	3.1	1382.0	1	JAN	0359	120	33.	13.1	1386.2	1	JAN	0719	220	34.	37.4	1394.8
1	JAN	0041	21	0.	3.1	1382.0	1	JAN	0401	121	38.	14.1	1386.6	1	JAN	0721	221	33.	37.4	1394.8
1	JAN	0043	22	0.	3.1	1382.0	1	JAN	0403	122	44.	15.2	1387.0	1	JAN	0723	222	31.	37.4	1394.8
1	JAN	0045	23	0.	3.2	1382.0	1	JAN	0405	123	51.	16.5	1387.5	1	JAN	0725	223	30.	37.4	1394.8
1	JAN	0047	24	0.	3.2	1382.0	1	JAN	0407	124	58.	18.2	1388.1	1	JAN	0727	224	29.	37.4	1394.8
1	JAN	0049	25	0.	3.2	1382.0	1	JAN	0409	125	63.	20.1	1388.8	1	JAN	0729	225	28.	37.4	1394.8
1	JAN	0051	26	0.	3.2	1382.0	1	JAN	0411	126	69.	22.4	1389.6	1	JAN	0731	226	27.	37.4	1394.8
1	JAN	0053	27	0.	3.2	1382.0	1	JAN	0413	127	75.	25.1	1390.5	1	JAN	0733	227	26.	37.4	1394.8
1	JAN	0055	28	0.	3.2	1382.0	1	JAN	0415	128	81.	28.3	1391.6	1	JAN	0735	228	25.	37.4	1394.8
1	JAN	0057	29	0.	3.2	1382.0	1	JAN	0417	129	131.	31.9	1392.7	1	JAN	0737	229	23.	37.4	1394.8
1	JAN	0059	30	0.	3.2	1382.0	1	JAN	0419	130	354.	35.6	1393.8	1	JAN	0739	230	22.	37.4	1394.8
1	JAN	0101	31	0.	3.2	1382.0	1	JAN	0421	131	1837.	37.4	1397.5	1	JAN	0741	231	21.	37.4	1394.8
1	JAN	0103	32	0.	3.2	1382.0	1	JAN	0423	132	1988.	37.4	1397.8	1	JAN	0743	232	20.	37.4	1394.8
1	JAN	0105	33	0.	3.2	1382.0	1	JAN	0425	133	2120.	37.4	1398.0	1	JAN	0745	233	19.	37.4	1394.8
1	JAN	0107	34	0.	3.2	1382.0	1	JAN	0427	134	2221.	37.4	1398.1	1	JAN	0747	234	18.	37.4	1394.8
1	JAN	0109	35	0.	3.2	1382.0	1	JAN	0429	135	2286.	37.4	1398.2	1	JAN	0749	235	17.	37.4	1394.8
1	JAN	0111	36	0.	3.2	1382.0	1	JAN	0431	136	2315.	37.4	1398.3	1	JAN	0751	236	16.	37.4	1394.8
1	JAN	0113	37	0.	3.2	1382.0	1	JAN	0433	137	2308.	37.4	1398.2	1	JAN	0753	237	15.	37.4	1394.8
1	JAN	0115	38	0.	3.2	1382.0	1	JAN	0435	138	2271.	37.4	1398.2	1	JAN	0755	238	14.	37.4	1394.8
1	JAN	0117	39	1.	3.2	1382.1	1	JAN	0437	139	2209.	37.4	1398.1	1	JAN	0757	239	13.	37.4	1394.8
1	JAN	0119	40	1.	3.3	1382.1	1	JAN	0439	140	2130.	37.4	1398.0	1	JAN	0759	240	13.	37.4	1394.8
1	JAN	0121	41	1.	3.3	1382.1	1	JAN	0441	141	2039.	37.4	1397.8	1	JAN	0801	241	12.	37.4	1394.8
1	JAN	0123	42	1.	3.3	1382.1	1	JAN	0443	142	1942.	37.4	1397.7	1	JAN	0803	242	12.	37.4	1394.8
1	JAN	0125	43	1.	3.3	1382.1	1	JAN	0445	143	1838.	37.4	1397.5	1	JAN	0805	243	11.	37.4	1394.8
1	JAN	0127	44	1.	3.3	1382.1	1	JAN	0447	144	1732.	37.4	1397.4	1	JAN	0807	244	10.	37.4	1394.8
1	JAN	0129	45	1.	3.4	1382.1	1	JAN	0449	145	1627.	37.4	1397.2	1	JAN	0809	245	10.	37.4	1394.8
1	JAN	0131	46	1.	3.4	1382.1	1	JAN	0451	146	1520.	37.4	1397.1	1	JAN	0811	246	9.	37.4	1394.8
1	JAN	0133	47	1.	3.4	1382.1	1	JAN	0453	147	1414.	37.4	1396.9	1	JAN	0813	247	9.	37.4	1394.8
1	JAN	0135	48	2.	3.5	1382.2	1	JAN	0455	148	1313.	37.4	1396.7	1	JAN	0815	248	8.	37.4	1394.8
1	JAN	0137	49	2.	3.5	1382.2	1	JAN	0457	149	1217.	37.4	1396.6	1	JAN	0817	249	8.	37.4	1394.8
1	JAN	0139	50	2.	3.6	1382.2	1	JAN	0459	150	1129.	37.4	1396.5	1	JAN	0819	250	8.	37.4	1394.8
1	JAN	0141	51	3.	3.7	1382.2	1	JAN	0501	151	1046.	37.4	1396.3	1	JAN	0821	251	7.	37.4	1394.8
1	JAN	0143	52	3.	3.8	1382.3	1	JAN	0503	152	968.	37.4	1396.2	1	JAN	0823	252	7.	37.4	1394.8
1	JAN	0145	53	3.	3.8	1382.3	1	JAN	0505	153	897.	37.4	1396.1	1	JAN	0825	253	7.	37.4	1394.8
1	JAN	0147	54	4.	3.9	1382.3	1	JAN	0507	154	827.	37.4	1396.0	1	JAN	0827	254	7.	37.4	1394.8
1	JAN	0149	55	4.	4.0	1382.4	1	JAN	0509	155	762.	37.4	1395.9	1	JAN	0829	255	6.	37.4	1394.8
1	JAN	0151	56	5.	4.1	1382.4	1	JAN	0511	156	706.	37.4	1395.8	1	JAN	0831	256	6.	37.4	1394.8
1	JAN	0153	57	5.	4.2	1382.5	1	JAN	0513	157	652.	37.4	1395.8	1	JAN	0833	257	6.	37.4	1394.8
1	JAN	0155	58	5.	4.3	1382.5	1	JAN	0515	158	601.	37.4	1395.7	1	JAN	0835	258	6.	37.4	1394.8
1	JAN	0157	59	6.	4.4	1382.6	1	JAN	0517	159	558.	37.4	1395.6	1	JAN	0837	259	5.	37.4	1394.8
1	JAN	0159	60	6.	4.5	1382.6	1	JAN	0519	160	521.	37.4	1395.6	1	JAN	0839	260	5.	37.4	1394.8
1	JAN	0201	61	7.	4.6	1382.6	1	JAN	0521	161	484.	37.4	1395.5	1	JAN	0841	261	5.	37.4	1394.8
1	JAN	0203	62	7.	4.7	1382.7	1	JAN	0523	162	449.	37.4	1395.5	1	JAN	0843	262	5.	37.4	1394.8
1	JAN	0205	63	8.	4.8	1382.7	1	JAN	0525	163	417.	37.4	1395.4	1	JAN	0845	263	4.	37.4	1394.8
1	JAN	0207	64	8.	4.9	1382.8	1	JAN	0527	164	390.	37.4	1395.4	1	JAN	0847	264	4.	37.4	1394.8
1	JAN	0209	65	9.	5.0	1382.8	1	JAN	0529	165	366.	37.4	1395.3	1	JAN	0849	265	4.	37.4	1394.8
1	JAN	0211	66	9.	5.1	1382.9	1	JAN	0531	166	341.	37.4	1395.3	1	JAN	0851	266	4.	37.4	1394.8
1	JAN	0213	67	9.	5.2	1382.9	1	JAN	0533	167	316.	37.4	1395.3	1	JAN	0853	267	4.	37.4	1394.8
1	JAN	0215	68	10.	5.3	1382.9	1	JAN	0535	168	293.	37.4	1395.2	1	JAN	0855	268	3.	37.4	1394.8
1	JAN	0217	69	10.	5.4	1383.0	1	JAN	0537	169										

+		CP2A1	2219.	4.40	348.	211.	211.	1.83		
+	ROUTED TO	RCP21	2213.	4.43	348.	211.	211.	1.83	3.99	4.43
+										
+	HYDROGRAPH AT	S2A2	32.	4.30	7.	4.	4.	.04		
+	2 COMBINED AT	CP2A2	2244.	4.43	355.	215.	215.	1.87		
+	ROUTED TO	RCP22	2244.	4.43	355.	215.	215.	1.87	5.51	4.43
+										
+	HYDROGRAPH AT	S2B	36.	4.07	4.	3.	3.	.03		
+	2 COMBINED AT	CP2B	2261.	4.43	359.	218.	218.	1.89		
+	ROUTED TO	RCP2B	2252.	4.47	359.	218.	218.	1.89	2.84	4.47
+										
+	HYDROGRAPH AT	S2C	37.	4.07	5.	3.	3.	.03		
+	2 COMBINED AT	CP2C	2268.	4.47	364.	221.	221.	1.92		
+	ROUTED TO	RCP2C	2268.	4.47	364.	221.	221.	1.92	3.49	4.47
+										
+	HYDROGRAPH AT	S2D	28.	4.10	4.	2.	2.	.02		
+	HYDROGRAPH AT	S2I	38.	4.07	5.	3.	3.	.03		
+	3 COMBINED AT	CP2D1	2301.	4.47	372.	226.	226.	1.97		
+	ROUTED TO	RCPDI	2291.	4.50	372.	226.	226.	1.97	3.65	4.50
+										
+	HYDROGRAPH AT	S2E	32.	4.17	6.	3.	3.	.03		
+	2 COMBINED AT	CP2E	2315.	4.50	378.	229.	229.	2.01		
+	ROUTED TO	BSN-A	2315.	4.50	310.	188.	188.	2.01	1398.25	4.50
+										
+	DIVERSION TO	DVRT1	151.	4.50	66.	41.	41.	2.01		
+	HYDROGRAPH AT	SPILL1	2164.	4.50	244.	147.	147.	2.01		

*** NORMAL END OF HEC-1 ***

-----DSS---ZCLOSE Unit: 71, File: TTM-NOW.DSS
 Pointer Utilization: .25
 Number of Records: 2
 File Size: 16.9 Kbytes
 Percent Inactive: .00

```

*****
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* SEPTEMBER 1990 *
* VERSION 4.0 *
* RUN DATE 07/10/1997 TIME 15:53:06 *
*****

```

```

*****
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*****

```

```

X X XXXXXXX XXXXX X
X X X X X XX
X X X X X X
XXXXXX XXXX X XXXXX X
X X X X X X
X X X X X X
X X XXXXXXX XXXXX XXX

```

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1GS, HEC1DB, AND HEC1KW.
 THE DEFINITIONS OF VARIABLES -RTIMP- AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE.
 THE DEFINITION OF -AMSK- ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION
 NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE, SINGLE EVENT DAMAGE CALCULATION, DSS:WRITE STAGE FREQUENCY,
 DSS:READ TIME SERIES AT DESIRED CALCULATION INTERVAL LOSS RATE:GREEN AND AMPT INFILTRATION
 KINEMATIC WAVE: NEW FINITE DIFFERENCE ALGORITHM

1 HEC-1 INPUT PAGE 1

```

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10
1 ID TATUM WASH PROJECT SUB-AREAS 1 AND 2 COMBINED - 2/9/95
2 ID 100YR-6HR STORM = 3.20". ASSUMED NORMAL CONDITION W/ DTHETA=0.250
3 ID STORM SIZE = 2.28 SQ. MI (TOTAL AREA)
4 ID HYDROGRAPH PLOT FOR 5 DETENTION BASIN SITES (*.DSS)
5 ID DETENTION BASIN A LOCATED SOUTH OF SHEA BLVD
6 ID SPILLWAY IS OVER THE S/W INTO THE ROAD
7 ID NO LOW FLOW OUTLET IINCLUDED FOR PERSEVE BASIN SIZING
8 ID FILE:TMM-NO.DAT
9 *DIAGRAM
IT 2 1JAN96 0001 2000
10 IO 5
11 KK S1B
12 KM SUB-BASIN S1B
13 KM 6-HOUR RAINFALL, PATTERN NO. 1.88 WAS USED TO FIND TC & R FOR THIS BASIN
14 KM THIS BASIN USED RAINFALL REDUCTION FACTOR OF .978
15 KO 5
16 BA .230
17 IN 15
18 KM RAINFALL DEPTH OF 3.20 WAS SPACIALLY REDUCED AS SHOWN BY THE PB RECORD
19 PB 3.131
20 KM THE FOLLOWING PC RECORD USED A 6-HOUR STORM WITH A PATTERN No. OF 1.88
21 PC .000 .009 .016 .025 .034 .042 .051 .059 .067 .076
22 PC .087 .100 .120 .160 .248 .442 .711 .846 .904 .939
23 PC .951 .964 .976 .988 1.000
24 LG .200 .250 4.300 .500 35.000
25 UC .363 .185
26 UA 0 3 5 8 12 20 43 75 90 96
27 UA 100
28 KK RS1B
29 KM ROUTING THROUGH SIC
30 KO 5
31 RS 3 FLOW -1
32 RC .035 .035 .035 2138 .028
33 RX 0 36 66 90 126 150 168 228
34 RY 7 7 7 0 0 4 6 22
35 KK S1A
36 KM SUB-BASIN S1A
37 KO 5
38 BA .330
39 LG .200 .250 4.300 .500 35.000
40 UC .363 .185
41 UA 0 3 5 8 12 20 43 75 90 96
42 UA 100
43 KK RS1A
44 KM ROUTING THROUGH SIC
45 KO 5
46 RS 3 FLOW -1
47 RC .035 .035 .035 2025 .030
48 RX 0 0.5 1 126 136 251 252 253
49 RY 5 5 5 0 5 5 5

```

1 HEC-1 INPUT PAGE 2

```

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10
50 KK SIC
51 KM SUB-BASIN SIC
52 KO 5
53 BA .110
54 LG .200 .250 4.300 .500 35.000
55 UC .329 .265
56 UA 0 3 5 8 12 20 43 75 90 96
57 UA 100
58 KK CP1C
59 KM ADDITION OF 3 HYDROGRAPHS

```

60	KM	POTENTIAL DETENTION BASIN SITE 1									
61	KO	5									
62	HC	3									
63	KK	RCPLC									
64	KM	ROUTING THROUGH SIE									
65	KO	5									
66	RS	5	FLOW	-1							
67	RC	.035	.035	.035	3600	.017					
68	RX	0	42	72	84	120	138	180	216		
69	RY	9	8.5	4	0	0	4	6	8		
70	KK	SID									
71	KM	SUB-BASIN SID									
72	KO	5									
73	BA	.310									
74	LG	.200	.250	4.300	.500	35.000					
75	UC	.363	.205								
76	UA	0	3	5	8	12	20	43	75	90 96	
77	UA	100									
78	KK	RSID									
79	KM	ROUTING THROUGH SIE									
80	KO	5									
81	RS	3	FLOW	-1							
82	RC	.035	.035	.035	2138	.019					
83	RX	0	36	72	96	132	168	204	240		
84	RY	8	6	4	0	0	8	10	11		
85	KK	SIE									
86	KM	SUB-BASIN SIE									
87	KO	5									
88	BA	.510									
89	LG	.200	.250	4.300	.500	35.000					
90	UC	.433	.242								
91	UA	0	3	5	8	12	20	43	75	90 96	
92	UA	100									

HEC-1 INPUT

PAGE 3

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

93	KK	CP1E									
94	KM	CONCENTRATION OF 3 HYDROGRAPHS									
95	KM	POTENTIAL DETENTION BASIN SITE 2									
96	KO	5									
97	HC	3									
98	KK	RCPIE									
99	KM	ROUTING THROUGH SIF									
100	KO	5									
101	RS	3	FLOW	-1							
102	RC	.035	.035	.035	2250	.014					
103	RX	0	48	84	120	144	180	240	288		
104	RY	12	10	6	2	0	8	10	11		
105	KK	SIF									
106	KM	SUB-BASIN SIF									
107	KO	5									
108	BA	.280									
109	LG	.200	.250	4.300	.500	35.000					
110	UC	.413	.300								
111	UA	0	3	5	8	12	20	43	75	90 96	
112	UA	100									
113	KK	CP1F									
114	KM	POTENTIAL DETENTION BASIN SITE 3									
115	KO	5									
116	HC	2									
117	KK	PARK									
118	KO	3									
119	KM	CITY OF PHX EQUESTRIAN PARK IN MTN PRESERVE									
120	KM	PROPOSED FUTURE PHASE OF TATUM WASH PROJECT									
121	DT	DIV1 145									
122	DI	0 10000									
123	DQ	0 10000									
124	KK	RCPI									
125	KO	5									
126	RS	2	FLOW	-1							
127	RC	.035	.03	.035	1100.0	0.0009					
128	RX	0	30	60	90	120	150	180	210		
129	RY	5	3	1	0	0	1	3	5		
130	KK	S2A1									
131	KM	SUB-BASIN S2A1									
132	KO	5									
133	BA	0.056									
134	LG	0.150	0.250	4.300	0.400	35.000					
135	UC	0.217	0.155								
136	UA	0	3	5	8	12	20	43	75	90 96	
137	UA	100									

HEC-1 INPUT

PAGE 4

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10


138	KK	CP2A1									
139	KM	COMBINE AT 40TH STREET									
140	KM	POTENTIAL DETENTION BASIN SITE 4									
141	KO	5									
142	HC	2									
143	KK	RCP21									
144	KO	5									
145	RS	2	FLOW	-1							
146	RC	.035	.03	.035	1360	.0162					

233	KK	CF2E												
234	KM	AT SHEA BLVD, POTENTIAL DETENTION BASIN SITE 5												
235	HC	2												
236	KK	BSN-A												
237	KO	2	0											
238	ZW	A=TATUM	B=INFLOW	C=FLOW	E=2MIN	F=WO								
239	KM	DETENTION BASIN LOCATED ON THE SOUTH SIDE OF SHEA BLVD												
240	ZW	A=TATUM	B=OUTFLOW	C=STAGE	E=2MIN	F=WO								
241	RS	1	STOR	-1										
242	SV	0	3.13	7.63	12.51	17.80	23.49	29.61	32.83	36.16	36.16			
243	SQ	0	0	0	0	0	0	0	0	126	802			
244	SE	1380.5	1382	1384	1386	1388	1390	1392	1393	1394	1395			
245	KK	SPILL1												
246	KM	ACTUAL LOW FLOWS GO TO SHEA STORM DRAIN												
247	KM	DIVERSION BASED UPON STAGED OUTLET												
248	KM	LOW FLOW WILL BE CONSIDERED FOR SIZING UPPER BASIN												
249	DT	DVRT1												
250	DI	0	50	132	2400									
251	DQ	0	0	0	1									
252	ZZ													

- No outFlow to S.D.

1

SCHEMATIC DIAGRAM OF STREAM NETWORK



```

190   CF2C.....
      V
      V
194   RCP2C
      .
      .
200   .           S2D
      .
      .
208   .           S2I
      .
      .
216   CF2DI.....
      V
      V
219   RCPDI
      .
      .
225   .           S2E
      .
      .
233   CF2E.....
      V
      V
236   BSN-A
      .
      .
249   ----->  DVRT1
245   SPILL1

```

(***) RUNOFF ALSO COMPUTED AT THIS LOCATION

```

*****
*
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
*
* SEPTEMBER 1990 *
*
* VERSION 4.0 *
*
* RUN DATE 07/10/1997 TIME 15:53:06 *
*
*****

```

```

U.S. ARMY CORPS OF ENGINEERS
HYDROLOGIC ENGINEERING CENTER
609 SECOND STREET
DAVIS, CALIFORNIA 95616
(916) 756-1104

```

TATUM WASH PROJECT SUB-AREAS 1 AND 2 COMBINED ~ 2/9/95
100YR-6HR STORM = 3.20". ASSUMED NORMAL CONDITION W/ DTHETA=0.250
STORM SIZE = 2.28 SQ. MI (TOTAL AREA)
HYDROGRAPH PLOT FOR 5 DETENTION BASIN SITES (*.DSS)
DETENTION BASIN A LOCATED SOUTH OF SHEA BLVD
SPILLWAY IS OVER THE S/W INTO THE ROAD
NO LOW FLOW OUTLET INCLUDED FOR PERSERVE BASIN SIZING
FILE:TTM-NO.DAT

*** ERROR *** SPECIFIED START AND END DATES RESULT IN TOO MANY TIME PERIODS

```

10 IO   OUTPUT CONTROL VARIABLES
        IPRNT      5   PRINT CONTROL
        IPLOT      0   PLOT CONTROL
        QSCAL      0.  HYDROGRAPH PLOT SCALE

IT      HYDROGRAPH TIME DATA
        NMIN       2   MINUTES IN COMPUTATION INTERVAL
        IDATE      1JAN96 STARTING DATE
        ITIME      0001 STARTING TIME
        NQ         300 NUMBER OF HYDROGRAPH ORDINATES
        NDDATE     1JAN96 ENDING DATE
        NDTIME     0959 ENDING TIME
        ICENT      19   CENTURY MARK

        COMPUTATION INTERVAL .03 HOURS
        TOTAL TIME BASE     9.97 HOURS

```

ENGLISH UNITS
DRAINAGE AREA SQUARE MILES
PRECIPITATION DEPTH INCHES
LENGTH, ELEVATION FEET
FLOW CUBIC FEET PER SECOND
STORAGE VOLUME ACRE-FEET
SURFACE AREA ACRES
TEMPERATURE DEGREES FAHRENHEIT

```

15 KO   OUTPUT CONTROL VARIABLES
        IPRNT      5   PRINT CONTROL
        IPLOT      0   PLOT CONTROL
        QSCAL      0.  HYDROGRAPH PLOT SCALE

30 KO   OUTPUT CONTROL VARIABLES
        IPRNT      5   PRINT CONTROL
        IPLOT      0   PLOT CONTROL
        QSCAL      0.  HYDROGRAPH PLOT SCALE

37 KO   OUTPUT CONTROL VARIABLES
        IPRNT      5   PRINT CONTROL
        IPLOT      0   PLOT CONTROL
        QSCAL      0.  HYDROGRAPH PLOT SCALE

45 KO   OUTPUT CONTROL VARIABLES

```

```

      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
52 KO  OUTPUT CONTROL VARIABLES
      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
61 KO  OUTPUT CONTROL VARIABLES
      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
65 KO  OUTPUT CONTROL VARIABLES
      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
72 KO  OUTPUT CONTROL VARIABLES
      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
80 KO  OUTPUT CONTROL VARIABLES
      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
87 KO  OUTPUT CONTROL VARIABLES
      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
96 KO  OUTPUT CONTROL VARIABLES
      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
100 KO OUTPUT CONTROL VARIABLES
      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
107 KO OUTPUT CONTROL VARIABLES
      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
115 KO OUTPUT CONTROL VARIABLES
      IFRNT      5  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE

```

```

*****
*          *
*   PARK   *
*          *
*****

```

```

118 KO  OUTPUT CONTROL VARIABLES
      IFRNT      3  PRINT CONTROL
      IPLOT      0  PLOT CONTROL
      QSCAL      0. HYDROGRAPH PLOT SCALE
      CITY OF PHX EQUESTRIAN PARK IN MTN PRESERVE
      PROPOSED FUTURE PHASE OF TATUM WASH PROJECT

```

```

DT  DIVERSION
    ISTDAD      DIV1  DIVERSION HYDROGRAPH IDENTIFICATION
    DSTRMX      145.00  MAXIMUM VOLUME TO BE DIVERTED
DI  INFLOW      .00  10000.00
DQ  DIVERTED FLOW .00  10000.00

```

		DIVERSION HYDROGRAPH DIV1			
PEAK FLOW	TIME	6-HR	MAXIMUM AVERAGE FLOW		9.97-HR
(CFS)	(HR)		24-HR	72-HR	
+	2212.	4.33	292.	176.	176.
			176.	176.	176.
			1.536	1.536	1.536
			145.	145.	145.
			(INCHES)		
			(AC-FT)		

CUMULATIVE AREA = 1.77 SQ MI

		HYDROGRAPH AT STATION PARK			
PEAK FLOW	TIME	6-HR	MAXIMUM AVERAGE FLOW		9.97-HR
(CFS)	(HR)		24-HR	72-HR	
+	592.	4.97	47.	28.	28.
			28.	28.	28.
			.247	.247	.247
			.23.	.23.	.23.
			(INCHES)		
			(AC-FT)		

CUMULATIVE AREA = 1.77 SQ MI

125 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

132 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

141 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

144 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

150 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

158 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

161 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

168 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

177 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

184 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

192 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

195 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

202 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

210 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

217 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

220 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

227 KO OUTPUT CONTROL VARIABLES
IPRNT 5 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE

*** **

236 KK *****
* BSN-A *

237 KO OUTPUT CONTROL VARIABLES
IPRNT 2 PRINT CONTROL
IPLOT 0 PLOT CONTROL
QSCAL 0. HYDROGRAPH PLOT SCALE
DETENTION BASIN LOCATED ON THE SOUTH SIDE OF SHEA BLVD

HYDROGRAPH ROUTING DATA

241 RS	STORAGE ROUTING	1	NUMBER OF SUBREACHES												
	NSTFS	STOR	TYPE OF INITIAL CONDITION												
	ITYP	-1.00	INITIAL CONDITION												
	RSVRIC	.00	WORKING R AND D COEFFICIENT												
	X														
242 SV	STORAGE	.0	3.1	7.6	12.5	17.8	23.5	29.6	32.8	36.2	36.2				
243 SQ	DISCHARGE	0.	0.	0.	0.	0.	0.	0.	0.	126.	893.				
244 SE	ELEVATION	1380.50	1382.00	1384.00	1386.00	1388.00	1390.00	1392.00	1393.00	1394.00	1395.00				

HYDROGRAPH AT STATION BSN-A

DA	MON	HRMN	ORD	OUTFLOW	STORAGE	STAGE	DA	MON	HRMN	ORD	OUTFLOW	STORAGE	STAGE	DA	MON	HRMN	ORD	OUTFLOW	STORAGE	
1	JAN	0001	1	0.	3.1	1382.0	1	JAN	0321	101	0.	3.8	1382.3	1	JAN	0641	201	87.	35.1	
1393.7	1	JAN	0003	2	0.	3.1	1382.0	1	JAN	0323	102	0.	3.9	1382.3	1	JAN	0643	202	85.	35.1
1393.7	1	JAN	0005	3	0.	3.1	1382.0	1	JAN	0325	103	0.	3.9	1382.3	1	JAN	0645	203	83.	35.0
1393.7	1	JAN	0007	4	0.	3.1	1382.0	1	JAN	0327	104	0.	3.9	1382.3	1	JAN	0647	204	81.	35.0
1393.6	1	JAN	0009	5	0.	3.1	1382.0	1	JAN	0329	105	0.	3.9	1382.3	1	JAN	0649	205	79.	34.9
1393.6	1	JAN	0011	6	0.	3.1	1382.0	1	JAN	0331	106	0.	3.9	1382.4	1	JAN	0651	206	78.	34.9
1393.6	1	JAN	0013	7	0.	3.1	1382.0	1	JAN	0333	107	0.	3.9	1382.4	1	JAN	0653	207	76.	34.8
1393.6	1	JAN	0015	8	0.	3.1	1382.0	1	JAN	0335	108	0.	4.0	1382.4	1	JAN	0655	208	74.	34.8
1393.6	1	JAN	0017	9	0.	3.1	1382.0	1	JAN	0337	109	0.	4.0	1382.4	1	JAN	0657	209	72.	34.7
1393.6	1	JAN	0019	10	0.	3.1	1382.0	1	JAN	0339	110	0.	4.0	1382.4	1	JAN	0659	210	70.	34.7
1393.6	1	JAN	0021	11	0.	3.1	1382.0	1	JAN	0341	111	0.	4.1	1382.4	1	JAN	0701	211	69.	34.6
1393.5	1	JAN	0023	12	0.	3.1	1382.0	1	JAN	0343	112	0.	4.1	1382.4	1	JAN	0703	212	67.	34.6
1393.5	1	JAN	0025	13	0.	3.1	1382.0	1	JAN	0345	113	0.	4.2	1382.5	1	JAN	0705	213	65.	34.5
1393.5	1	JAN	0027	14	0.	3.1	1382.0	1	JAN	0347	114	0.	4.3	1382.5	1	JAN	0707	214	63.	34.5
1393.5	1	JAN	0029	15	0.	3.1	1382.0	1	JAN	0349	115	0.	4.3	1382.5	1	JAN	0709	215	61.	34.4
1393.5	1	JAN	0031	16	0.	3.1	1382.0	1	JAN	0351	116	0.	4.5	1382.6	1	JAN	0711	216	59.	34.4
1393.5	1	JAN	0033	17	0.	3.1	1382.0	1	JAN	0353	117	0.	4.6	1382.7	1	JAN	0713	217	57.	34.3
1393.5	1	JAN	0035	18	0.	3.1	1382.0	1	JAN	0355	118	0.	4.8	1382.7	1	JAN	0715	218	56.	34.3
1393.4	1	JAN	0037	19	0.	3.1	1382.0	1	JAN	0357	119	0.	5.0	1382.8	1	JAN	0717	219	54.	34.2
1393.4	1	JAN	0039	20	0.	3.1	1382.0	1	JAN	0359	120	0.	5.3	1383.0	1	JAN	0719	220	52.	34.2
1393.4	1	JAN	0041	21	0.	3.1	1382.0	1	JAN	0401	121	0.	5.6	1383.1	1	JAN	0721	221	50.	34.2
1393.4	1	JAN	0043	22	0.	3.1	1382.0	1	JAN	0403	122	0.	6.0	1383.3	1	JAN	0723	222	48.	34.1
1393.4	1	JAN	0045	23	0.	3.2	1382.0	1	JAN	0405	123	0.	6.5	1383.5	1	JAN	0725	223	47.	34.1
1393.4	1	JAN	0047	24	0.	3.2	1382.0	1	JAN	0407	124	0.	7.0	1383.7	1	JAN	0727	224	45.	34.0
1393.4	1	JAN	0049	25	0.	3.2	1382.0	1	JAN	0409	125	0.	7.6	1384.0	1	JAN	0729	225	43.	34.0
1393.3	1	JAN	0051	26	0.	3.2	1382.0	1	JAN	0411	126	0.	8.3	1384.3	1	JAN	0731	226	42.	33.9
1393.3	1	JAN	0053	27	0.	3.2	1382.0	1	JAN	0413	127	0.	8.9	1384.5	1	JAN	0733	227	40.	33.9
1393.3	1	JAN	0055	28	0.	3.2	1382.0	1	JAN	0415	128	0.	9.7	1384.8	1	JAN	0735	228	39.	33.9
1393.3	1	JAN	0057	29	0.	3.2	1382.0	1	JAN	0417	129	0.	10.4	1385.1	1	JAN	0737	229	37.	33.8
1393.3	1	JAN	0059	30	0.	3.2	1382.0	1	JAN	0419	130	0.	11.1	1385.4	1	JAN	0739	230	36.	33.8
1393.3	1	JAN	0101	31	0.	3.2	1382.0	1	JAN	0421	131	0.	11.8	1385.7	1	JAN	0741	231	34.	33.7
1393.3	1	JAN	0103	32	0.	3.2	1382.0	1	JAN	0423	132	0.	12.5	1386.0	1	JAN	0743	232	33.	33.7
1393.3	1	JAN	0105	33	0.	3.2	1382.0	1	JAN	0425	133	0.	13.2	1386.3	1	JAN	0745	233	32.	33.7
1393.3	1	JAN	0107	34	0.	3.2	1382.0	1	JAN	0427	134	0.	13.9	1386.5	1	JAN	0747	234	30.	33.6
1393.2	1	JAN	0109	35	0.	3.2	1382.0	1	JAN	0429	135	0.	14.5	1386.7	1	JAN	0749	235	29.	33.6
1393.2	1	JAN	0111	36	0.	3.2	1382.0	1	JAN	0431	136	0.	15.1	1387.0	1	JAN	0751	236	28.	33.6
1393.2	1	JAN	0113	37	0.	3.2	1382.0	1	JAN	0433	137	0.	15.6	1387.2	1	JAN	0753	237	27.	33.5
1393.2	1	JAN	0115	38	0.	3.2	1382.0	1	JAN	0435	138	0.	16.2	1387.4	1	JAN	0755	238	25.	33.5
1393.2	1	JAN	0117	39	0.	3.2	1382.0	1	JAN	0437	139	0.	16.6	1387.6	1	JAN	0757	239	24.	33.5

1393.0	1 JAN 0307 94	0.	3.7	1382.3	*	1 JAN 0627 194	100.	35.5	1393.8	*	1 JAN 0947 294	1.	32.9
1393.0	1 JAN 0309 95	0.	3.8	1382.3	*	1 JAN 0629 195	98.	35.4	1393.8	*	1 JAN 0949 295	1.	32.9
1393.0	1 JAN 0311 96	0.	3.8	1382.3	*	1 JAN 0631 196	96.	35.4	1393.8	*	1 JAN 0951 296	1.	32.9
1393.0	1 JAN 0313 97	0.	3.8	1382.3	*	1 JAN 0633 197	94.	35.3	1393.7	*	1 JAN 0953 297	1.	32.9
1393.0	1 JAN 0315 98	0.	3.8	1382.3	*	1 JAN 0635 198	92.	35.3	1393.7	*	1 JAN 0955 298	1.	32.9
1393.0	1 JAN 0317 99	0.	3.8	1382.3	*	1 JAN 0637 199	90.	35.2	1393.7	*	1 JAN 0957 299	1.	32.9
1393.0	1 JAN 0319 100	0.	3.8	1382.3	*	1 JAN 0639 200	88.	35.2	1393.7	*	1 JAN 0959 300	1.	32.9

```

*****
PEAK FLOW      TIME      6-HR      MAXIMUM AVERAGE FLOW      9.97-HR
+ (CFS)        (HR)                24-HR      72-HR
+ 111.         6.17              29.        17.        17.        17.
                (INCHES)         .133       .133       .133       .133
                (AC-FT)         14.        14.        14.        14.

PEAK STORAGE   TIME      6-HR      MAXIMUM AVERAGE STORAGE      9.97-HR
+ (AC-FT)      (HR)                24-HR      72-HR
+ 36.          6.17              29.        19.        19.        19.

PEAK STAGE     TIME      6-HR      MAXIMUM AVERAGE STAGE      9.97-HR
+ (FEET)       (HR)                24-HR      72-HR
+ 1393.88      6.17              1391.81   1387.97   1387.97   1387.97

CUMULATIVE AREA = 2.01 SQ MI

```

```

-----DSS---ZOPEN: Version: 6-EA; Existing File Opened
                    Unit: 71. File: TTM-NO.DSS
-----DSS---ZWRITE Unit 71; Vers. 7: /TATUM/OUTFLOW/FLOW/01JAN1996/2MIN/WO/
-----DSS---ZWRITE Unit 71; Vers. 7: /TATUM/OUTFLOW/STAGE/01JAN1996/2MIN/WO/
1

```

```

RUNOFF SUMMARY
FLOW IN CUBIC FEET PER SECOND
TIME IN HOURS, AREA IN SQUARE MILES

```

OPERATION	STATION	PEAK FLOW	TIME OF PEAK	AVERAGE FLOW FOR MAXIMUM PERIOD			BASIN AREA	MAXIMUM STAGE	TIME OF MAX STAGE
				6-HOUR	24-HOUR	72-HOUR			
HYDROGRAPH AT	S1B	319.	4.20	44.	27.	27.	.23		
ROUTED TO	RS1B	311.	4.27	44.	27.	27.	.23	1.04	4.27
HYDROGRAPH AT	S1A	458.	4.20	63.	38.	38.	.33		
ROUTED TO	RS1A	450.	4.27	63.	38.	38.	.33	1.49	4.27
HYDROGRAPH AT	S1C	138.	4.20	21.	13.	13.	.11		
3 COMBINED AT	CP1C	892.	4.27	128.	77.	77.	.67		
ROUTED TO	RCP1C	881.	4.33	128.	77.	77.	.67	2.30	4.33
HYDROGRAPH AT	S1D	418.	4.20	59.	36.	36.	.31		
ROUTED TO	RS1D	413.	4.27	59.	36.	36.	.31	1.40	4.27
HYDROGRAPH AT	S1E	647.	4.27	97.	59.	59.	.51		
3 COMBINED AT	CP1E	1911.	4.30	284.	172.	172.	1.49		
ROUTED TO	RCP1E	1895.	4.33	284.	172.	172.	1.49	5.06	4.33
HYDROGRAPH AT	S1F	331.	4.27	53.	32.	32.	.28		
2 COMBINED AT	CP1F	2212.	4.33	337.	204.	204.	1.77		
DIVERSION TO	DIV1	2212.	4.97	292.	176.	176.	1.77		
HYDROGRAPH AT	PARK	592.	4.97	47.	28.	28.	1.77		
ROUTED TO	RCP1	399.	5.17	47.	28.	28.	1.77	2.20	5.17

+	HYDROGRAPH AT	S2A1	88.	4.10	11.	7.	7.	.06		
+	2 COMBINED AT	CP2A1	402.	5.17	58.	35.	35.	1.83		
+	ROUTED TO	RCP21	398.	5.20	58.	35.	35.	1.83	1.77	5.20
+	HYDROGRAPH AT	S2A2	32.	4.30	7.	4.	4.	.04		
+	2 COMBINED AT	CP2A2	408.	5.20	64.	39.	39.	1.87		
+	ROUTED TO	RCP22	403.	5.23	64.	39.	39.	1.87	2.18	5.23
+	HYDROGRAPH AT	S2B	36.	4.07	4.	3.	3.	.03		
+	2 COMBINED AT	CP2B	404.	5.23	69.	42.	42.	1.89		
+	ROUTED TO	RCP2B	394.	5.27	69.	42.	42.	1.89	1.22	5.27
+	HYDROGRAPH AT	S2C	37.	4.07	5.	3.	3.	.03		
+	2 COMBINED AT	CP2C	395.	5.27	73.	45.	45.	1.92		
+	ROUTED TO	RCP2C	392.	5.30	73.	45.	45.	1.92	1.62	5.30
+	HYDROGRAPH AT	S2D	28.	4.10	4.	2.	2.	.02		
+	HYDROGRAPH AT	S2I	38.	4.07	5.	3.	3.	.03		
+	3 COMBINED AT	CP2DI	394.	5.30	82.	50.	50.	1.97		
+	ROUTED TO	RCPDI	379.	5.40	82.	50.	50.	1.97	1.54	5.40
+	HYDROGRAPH AT	S2E	32.	4.17	6.	3.	3.	.03		
+	2 COMBINED AT	CP2E	383.	5.40	87.	53.	53.	2.01		
+	ROUTED TO	BSN-A	111.	6.17	29.	17.	17.	2.01	1393.88	6.17
+	DIVERSION TO	DVRT1	0.	6.17	0.	0.	0.	2.01		
+	HYDROGRAPH AT	SPILL1	111.	6.17	29.	17.	17.	2.01		

*** NORMAL END OF HEC-1 ***

No Out-Flow to S.D.

-----DSS-----ZCLOSE Unit: 71, File: TTM-NO.DSS
 Pointer Utilization: .25
 Number of Records: 2
 File Size: 16.9 Kbytes
 Percent Inactive: .00

```

*****
* FLOOD HYDROGRAPH PACKAGE (HEC-1)
* SEPTEMBER 1990
* VERSION 4.0
* RUN DATE 07/22/1997 TIME 15:37:28
*****

```

```

*****
* U.S. ARMY CORPS OF ENGINEERS
* HYDROLOGIC ENGINEERING CENTER
* 609 SECOND STREET
* DAVIS, CALIFORNIA 95616
* (916) 756-1104
*****

```

```

X X XXXXXXX XXXXX X
X X X X X XX
X X X X X X
XXXXXX XXXX X XXXXX X
X X X X X X
X X X X X X
X X XXXXXXX XXXXX XXX

```

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1GS, HEC1DB, AND HEC1KW.

THE DEFINITIONS OF VARIABLES -RTIMP- AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE. THE DEFINITION OF -AMSKK- ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION

NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE, SINGLE EVENT DAMAGE CALCULATION, DSS:WRITE STAGE FREQUENCY, DSS:READ TIME SERIES AT DESIRED CALCULATION INTERVAL LOSS RATE:GREEN AND AMPT INFILTRATION

KINEMATIC WAVE: NEW FINITE DIFFERENCE ALGORITHM

1

HEC-1 INPUT

```

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10
1 ID TATUM WASH PROJECT SUB-AREAS 1 AND 2 COMBINED - 2/9/95
2 ID 100YR-6HR STORM = 3.20". ASSUMED NORMAL CONDITION W/ DTHETA=0.250
3 ID STORM SIZE = 2.28 SQ. MI (TOTAL AREA)
4 ID HYDROGRAPH PLOT FOR 5 DETENTION BASIN SITES (*.DSS)
5 ID DETENTION BASIN A LOCATED SOUTH OF SHEA BLVD
6 ID SPILLWAY IS OVER THE S/W INTO THE ROAD
7 ID OUTLET IS A THREE STAGED ORIFICE
8 ID FILE:TTM-100.DAT
*DIAGRAM
9 IT 2 1JAN96 0001 2000
10 IO 5
11 KK S1B
12 KM SUB-BASIN S1B
13 KM 6-HOUR RAINFALL, PATTERN NO. 1.88 WAS USED TO FIND TC & R FOR THIS BASIN
14 KM THIS BASIN USED RAINFALL REDUCTION FACTOR OF .978
15 KO 5
16 BA .230
17 IN 15
18 KM RAINFALL DEPTH OF 3.20 WAS SPACIALLY REDUCED AS SHOWN BY THE FB RECORD
19 FB 3.131
20 KM THE FOLLOWING FC RECORD USED A 6-HOUR STORM WITH A PATTERN No. OF 1.88
21 FC .000 .009 .016 .025 .034 .042 .051 .059 .067 .076
22 FC .087 .100 .120 .160 .248 .442 .711 .846 .904 .939
23 FC .951 .964 .976 .988 1.000
24 LG .200 .250 4.300 .500 35.000
25 UC .363 .185
26 UA 0 3 5 8 12 20 43 75 90 96
27 UA 100
28 KK RS1B
29 KM ROUTING THROUGH SIC
30 KO 5
31 RS 3 FLOW -1
32 RC .035 .035 .035 2138 .028
33 RX 0 36 66 90 126 150 168 228
34 RY 7 7 7 0 0 4 6 22
35 KK S1A
36 KM SUB-BASIN S1A
37 KO 5
38 BA .330
39 LG .200 .250 4.300 .500 35.000
40 UC .363 .185
41 UA 0 3 5 8 12 20 43 75 90 96
42 UA 100
43 KK RS1A
44 KM ROUTING THROUGH SIC
45 KO 5
46 RS 3 FLOW -1
47 RC .035 .035 .035 2025 .030
48 RX 0 0.5 1 126 136 251 252 253
49 RY 5 5 5 0 0 5 5 5

```

1

HEC-1 INPUT

```

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10
50 KK SIC
51 KM SUB-BASIN SIC
52 KO 5
53 BA .110
54 LG .200 .250 4.300 .500 35.000
55 UC .329 .265
56 UA 0 3 5 8 12 20 43 75 90 96
57 UA 100
58 KK CPIC
59 KM ADDITION OF 3 HYDROGRAPHS

```


233	KK	CF2E												
234	KM	AT SHEA BLVD, POTENTIAL DETENTION BASIN SITE 5												
235	HC	2												
236	KK	BSN-A												
237	KO	2	0											
238	ZW	A=TATUM	B=INFLOW	C=FLOW	E=2MIN	F=WO								
239	KM	DETENTION BASIN LOCATED ON THE SOUTH SIDE OF SHEA BLVD												
240	ZW	A=TATUM	B=OUTFLOW	C=STAGE	E=2MIN	F=WO								
241	RS	1	STOR	-1										
242	SV	0	3.13	7.63	12.51	17.80	23.49	29.61	32.83	36.16	36.16			
243	SQ	0	0	21	30	57	72	83	151	395	1061			
244	SE	1380.5	1382	1384	1386	1388	1390	1392	1393	1394	1395			
245	KK	SPILL												
246	KM	ACTUAL LOW FLOWS GO TO SHEA STORM DRAIN												
247	KM	DIVERSION BASED UPON STAGED OUTLET												
248	KM	LOW FLOW WILL BE CONSIDERED FOR SIZING UPPER BASIN												
249	DT	DVRT1												
250	DI	0	50	83	395	2400								
251	DQ	0	50	83	151	151								
252	ZZ													

1

SCHEMATIC DIAGRAM OF STREAM NETWORK

INPUT LINE	(V) ROUTING	(--->) DIVERSION OR PUMP FLOW
NO.	(.) CONNECTOR	(<---) RETURN OF DIVERTED OR PUMPED FLOW
11	S1B	
	v	
	v	
28	RS1B	
	.	
	.	
35	S1A	
	v	
	v	
43	RS1A	
	.	
	.	
50		S1C
	.	
	.	
58	CP1C.....	
	v	
	v	
63	RCP1C	
	.	
	.	
70	S1D	
	v	
	v	
78	RS1D	
	.	
	.	
85		S1E
	.	
	.	
93	CP1E.....	
	v	
	v	
98	RCP1E	
	.	
	.	
105	S1F	
	.	
	.	
113	CP1F.....	
	.	
	.	
121	----->	DIV1
117	PARK	
	v	
	v	
124	RCP1	
	.	
	.	
130	S2A1	
	.	
	.	
138	CP2A1.....	
	v	
	v	
143	RCP21	
	.	
	.	
149	S2A2	
	.	
	.	
156	CP2A2.....	
	v	
	v	
160	RCP22	
	.	
	.	
166	S2B	
	.	
	.	
174	CP2B.....	
	v	
	v	
176	RCP2B	
	.	
	.	
182	S2C	
	.	

```

190      CF2C.....
      V
      V
194      RCF2C
      .
      .
200      .          S2D
      .          .
      .          .
208      .          .          S2I
      .          .          .
      .          .          .
216      CF2DI.....
      V
      V
219      RCFDI
      .
      .
225      .          S2E
      .          .
      .          .
233      CF2E.....
      V
      V
236      BGN-A
      .
      .
249      -----> DVRT1
245      SPILLI

```

(***) RUNOFF ALSO COMPUTED AT THIS LOCATION

```

*****
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* SEPTEMBER 1990 *
* VERSION 4.0 *
* RUN DATE 07/22/1997 TIME 15:37:28 *
*****

```

```

*****
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*****

```

TATUM WASH PROJECT SUB-AREAS 1 AND 2 COMBINED - 2/9/95
100YR-6HR STORM = 3.20". ASSUMED NORMAL CONDITION W/ DTHETA=0.250
STORM SIZE = 2.28 SQ. MI (TOTAL AREA)
HYDROGRAPH PLOT FOR 5 DETENTION BASIN SITES (*.DSS)
DETENTION BASIN A LOCATED SOUTH OF SHEA BLVD
SPILLWAY IS OVER THE S/W INTO THE ROAD
OUTLET IS A THREE STAGED ORIFICE
FILE:TIM-100.DAT

*** ERROR *** SPECIFIED START AND END DATES RESULT IN TOO MANY TIME PERIODS

```

10 IO      OUTPUT CONTROL VARIABLES
          IFRNT      5 PRINT CONTROL
          IFLOT      0 PLOT CONTROL
          QSCAL      0. HYDROGRAPH PLOT SCALE

IT        HYDROGRAPH TIME DATA
          NMIN       2 MINUTES IN COMPUTATION INTERVAL
          IDATE      1JAN96 STARTING DATE
          ITIME      0001 STARTING TIME
          NQ         300 NUMBER OF HYDROGRAPH ORDINATES
          NDDATE     1JAN96 ENDING DATE
          NDTIME     0959 ENDING TIME
          ICENT      19 CENTURY MARK

          COMPUTATION INTERVAL .03 HOURS
          TOTAL TIME BASE     9.97 HOURS

```

ENGLISH UNITS
DRAINAGE AREA SQUARE MILES
PRECIPITATION DEPTH INCHES
LENGTH, ELEVATION FEET
FLOW CUBIC FEET PER SECOND
STORAGE VOLUME ACRE-FEET
SURFACE AREA ACRES
TEMPERATURE DEGREES FAHRENHEIT

```

15 KO      OUTPUT CONTROL VARIABLES
          IFRNT      5 PRINT CONTROL
          IFLOT      0 PLOT CONTROL
          QSCAL      0. HYDROGRAPH PLOT SCALE

30 KO      OUTPUT CONTROL VARIABLES
          IFRNT      5 PRINT CONTROL
          IFLOT      0 PLOT CONTROL
          QSCAL      0. HYDROGRAPH PLOT SCALE

37 KO      OUTPUT CONTROL VARIABLES
          IFRNT      5 PRINT CONTROL
          IFLOT      0 PLOT CONTROL
          QSCAL      0. HYDROGRAPH PLOT SCALE

45 KO      OUTPUT CONTROL VARIABLES
          IFRNT      5 PRINT CONTROL
          IFLOT      0 PLOT CONTROL
          QSCAL      0. HYDROGRAPH PLOT SCALE

52 KO      OUTPUT CONTROL VARIABLES
          IFRNT      5 PRINT CONTROL
          IFLOT      0 PLOT CONTROL
          QSCAL      0. HYDROGRAPH PLOT SCALE

```

```

61 KO      OUTPUT CONTROL VARIABLES
           IPRNT      5  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE

65 KO      OUTPUT CONTROL VARIABLES
           IPRNT      5  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE

72 KO      OUTPUT CONTROL VARIABLES
           IPRNT      5  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE

80 KO      OUTPUT CONTROL VARIABLES
           IPRNT      5  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE

87 KO      OUTPUT CONTROL VARIABLES
           IPRNT      5  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE

96 KO      OUTPUT CONTROL VARIABLES
           IPRNT      5  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE

100 KO     OUTPUT CONTROL VARIABLES
           IPRNT      5  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE

107 KO     OUTPUT CONTROL VARIABLES
           IPRNT      5  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE

115 KO     OUTPUT CONTROL VARIABLES
           IPRNT      5  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE

```

```

*****
*          *
*   PARK   *
*          *
*****

```

```

118 KO     OUTPUT CONTROL VARIABLES
           IPRNT      3  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE
           CITY OF PHX EQUESTRIAN PARK IN MTN PRESERVE
           PROPOSED FUTURE PHASE OF TATUM WASH PROJECT

```

```

DT         DIVERSION
           ISTDAD      DIV1  DIVERSION HYDROGRAPH IDENTIFICATION
           DSTRMX     145.00  MAXIMUM VOLUME TO BE DIVERTED

DI         INFLOW      .00  10000.00

DQ         DIVERTED FLOW .00  10000.00

```

```

***          ***          ***          ***          ***

          DIVERSION HYDROGRAPH          DIV1
PEAK FLOW  TIME          6-HR  MAXIMUM AVERAGE FLOW  9.97-HR
+ (CFS)    (HR)          (CFS)  24-HR  72-HR
+ 2212.    4.33          292.    176.    176.    176.
          (INCHES)  1.536  1.536  1.536  1.536
          (AC-FT)  145.    145.    145.    145.
          CUMULATIVE AREA = 1.77 SQ MI

```

*** *** *** *** ***

```

          HYDROGRAPH AT STATION          PARK
PEAK FLOW  TIME          6-HR  MAXIMUM AVERAGE FLOW  9.97-HR
+ (CFS)    (HR)          (CFS)  24-HR  72-HR
+ 592.     4.97          47.    28.    28.    28.
          (INCHES)  .247  .247  .247  .247
          (AC-FT)  23.    23.    23.    23.
          CUMULATIVE AREA = 1.77 SQ MI

```

```

125 KO     OUTPUT CONTROL VARIABLES
           IPRNT      5  PRINT CONTROL
           IPLOT      0  PLOT CONTROL
           QSCAL      0.  HYDROGRAPH PLOT SCALE

```

```

132 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

141 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

144 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

150 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

158 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

161 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

168 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

177 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

184 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

192 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

195 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

202 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

210 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

217 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

220 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

227 KO      OUTPUT CONTROL VARIABLES
            IPRNT      5  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE

```

*** **

```

*****
*      *
*      *
236 KK *  BSN-A *
*      *
*****

```

```

237 KO      OUTPUT CONTROL VARIABLES
            IPRNT      2  PRINT CONTROL
            IPLOT      0  PLOT CONTROL
            QSCAL      0.  HYDROGRAPH PLOT SCALE
            DETENTION BASIN LOCATED ON THE SOUTH SIDE OF SHEA BLVD

```

HYDROGRAPH ROUTING DATA

```

241 RS      STORAGE ROUTING
            NSTPS      1  NUMBER OF SUBREACHES
            ITYP        STOR  TYPE OF INITIAL CONDITION
            RSVRIC      -1.00 INITIAL CONDITION
            X            .00 WORKING R AND D COEFFICIENT

```

```

242 SV      STORAGE      .0      3.1      7.6      12.5      17.8      23.5      29.6      32.8      36.2      36.2

```

243 SQ	DISCHARGE	0.	0.	21.	30.	57.	72.	83.	151.	395.	1061.
244 SE	ELEVATION	1380.50	1382.00	1384.00	1386.00	1388.00	1390.00	1392.00	1393.00	1394.00	1395.00

HYDROGRAPH AT STATION BSN-A

DA	MON	HRMN	ORD	OUTFLOW	STORAGE	STAGE	DA	MON	HRMN	ORD	OUTFLOW	STORAGE	STAGE	DA	MON	HRMN	ORD	OUTFLOW	STORAGE	STAGE
1	JAN	0001	1	0.	3.1	1382.0	1	JAN	0321	101	2.	3.6	1382.2	1	JAN	0641	201	82.	29.0	1391.8
1	JAN	0003	2	0.	3.1	1382.0	1	JAN	0323	102	2.	3.6	1382.2	1	JAN	0643	202	82.	29.0	1391.8
1	JAN	0005	3	0.	3.1	1382.0	1	JAN	0325	103	2.	3.6	1382.2	1	JAN	0645	203	82.	29.0	1391.8
1	JAN	0007	4	0.	3.1	1382.0	1	JAN	0327	104	2.	3.6	1382.2	1	JAN	0647	204	82.	28.9	1391.8
1	JAN	0009	5	0.	3.1	1382.0	1	JAN	0329	105	2.	3.6	1382.2	1	JAN	0649	205	82.	28.9	1391.8
1	JAN	0011	6	0.	3.1	1382.0	1	JAN	0331	106	2.	3.7	1382.2	1	JAN	0651	206	82.	28.8	1391.7
1	JAN	0013	7	0.	3.1	1382.0	1	JAN	0333	107	3.	3.7	1382.2	1	JAN	0653	207	81.	28.7	1391.7
1	JAN	0015	8	0.	3.1	1382.0	1	JAN	0335	108	3.	3.7	1382.2	1	JAN	0655	208	81.	28.7	1391.7
1	JAN	0017	9	0.	3.1	1382.0	1	JAN	0337	109	3.	3.7	1382.3	1	JAN	0657	209	81.	28.6	1391.7
1	JAN	0019	10	0.	3.1	1382.0	1	JAN	0339	110	3.	3.7	1382.3	1	JAN	0659	210	81.	28.5	1391.6
1	JAN	0021	11	0.	3.1	1382.0	1	JAN	0341	111	3.	3.8	1382.3	1	JAN	0701	211	81.	28.5	1391.6
1	JAN	0023	12	0.	3.1	1382.0	1	JAN	0343	112	3.	3.8	1382.3	1	JAN	0703	212	81.	28.4	1391.6
1	JAN	0025	13	0.	3.1	1382.0	1	JAN	0345	113	3.	3.9	1382.3	1	JAN	0705	213	81.	28.3	1391.6
1	JAN	0027	14	0.	3.1	1382.0	1	JAN	0347	114	4.	3.9	1382.4	1	JAN	0707	214	80.	28.2	1391.5
1	JAN	0029	15	0.	3.1	1382.0	1	JAN	0349	115	4.	4.0	1382.4	1	JAN	0709	215	80.	28.1	1391.5
1	JAN	0031	16	0.	3.1	1382.0	1	JAN	0351	116	5.	4.1	1382.4	1	JAN	0711	216	80.	28.0	1391.5
1	JAN	0033	17	0.	3.1	1382.0	1	JAN	0353	117	5.	4.2	1382.5	1	JAN	0713	217	80.	27.9	1391.4
1	JAN	0035	18	0.	3.1	1382.0	1	JAN	0355	118	6.	4.4	1382.6	1	JAN	0715	218	80.	27.8	1391.4
1	JAN	0037	19	0.	3.1	1382.0	1	JAN	0357	119	7.	4.6	1382.7	1	JAN	0717	219	79.	27.6	1391.4
1	JAN	0039	20	0.	3.1	1382.0	1	JAN	0359	120	8.	4.9	1382.8	1	JAN	0719	220	79.	27.5	1391.3
1	JAN	0041	21	0.	3.1	1382.0	1	JAN	0401	121	9.	5.2	1382.9	1	JAN	0721	221	79.	27.4	1391.3
1	JAN	0043	22	0.	3.1	1382.0	1	JAN	0403	122	11.	5.5	1383.1	1	JAN	0723	222	79.	27.3	1391.2
1	JAN	0045	23	0.	3.2	1382.0	1	JAN	0405	123	13.	6.0	1383.3	1	JAN	0725	223	79.	27.1	1391.2
1	JAN	0047	24	0.	3.2	1382.0	1	JAN	0407	124	15.	6.5	1383.5	1	JAN	0727	224	78.	27.0	1391.1
1	JAN	0049	25	0.	3.2	1382.0	1	JAN	0409	125	18.	7.0	1383.7	1	JAN	0729	225	78.	26.9	1391.1
1	JAN	0051	26	0.	3.2	1382.0	1	JAN	0411	126	21.	7.6	1384.0	1	JAN	0731	226	78.	26.7	1391.1
1	JAN	0053	27	0.	3.2	1382.0	1	JAN	0413	127	22.	8.2	1384.2	1	JAN	0733	227	78.	26.6	1391.0
1	JAN	0055	28	0.	3.2	1382.0	1	JAN	0415	128	23.	8.9	1384.5	1	JAN	0735	228	77.	26.4	1391.0
1	JAN	0057	29	0.	3.2	1382.0	1	JAN	0417	129	25.	9.5	1384.8	1	JAN	0737	229	77.	26.3	1390.9
1	JAN	0059	30	0.	3.2	1382.0	1	JAN	0419	130	26.	10.2	1385.1	1	JAN	0739	230	77.	26.1	1390.9
1	JAN	0101	31	0.	3.2	1382.0	1	JAN	0421	131	27.	10.8	1385.3	1	JAN	0741	231	77.	26.0	1390.8
1	JAN	0103	32	0.	3.2	1382.0	1	JAN	0423	132	28.	11.5	1385.6	1	JAN	0743	232	76.	25.8	1390.8
1	JAN	0105	33	0.	3.2	1382.0	1	JAN	0425	133	29.	12.1	1385.8	1	JAN	0745	233	76.	25.7	1390.7
1	JAN	0107	34	0.	3.2	1382.0	1	JAN	0427	134	31.	12.7	1386.1	1	JAN	0747	234	76.	25.5	1390.7
1	JAN	0109	35	0.	3.2	1382.0	1	JAN	0429	135	33.	13.2	1386.3	1	JAN	0749	235	75.	25.4	1390.6
1	JAN	0111	36	0.	3.2	1382.0	1	JAN	0431	136	36.	13.7	1386.4	1	JAN	0751	236	75.	25.2	1390.6
1	JAN	0113	37	0.	3.2	1382.0	1	JAN	0433	137	38.	14.1	1386.6	1	JAN	0753	237	75.	25.0	1390.5
1	JAN	0115	38	0.	3.2	1382.0	1	JAN	0435	138	40.	14.5	1386.8	1	JAN	0755	238	74.	24.9	1390.5
1	JAN	0117	39	0.	3.2	1382.0	1	JAN	0437	139	42.	14.9	1386.9	1	JAN	0757	239	74.	24.7	1390.4
1	JAN	0119	40	0.	3.2	1382.0	1	JAN	0439	140	44.	15.2	1387.0	1	JAN	0759	240	74.	24.5	1390.3
1	JAN	0121	41	1.	3.2	1382.0	1	JAN	0441	141	45.	15.5	1387.1	1	JAN	0801	241	74.	24.4	1390.3
1	JAN	0123	42	1.	3.2	1382.1	1	JAN	0443	142	47.	15.8	1387.3	1	JAN	0803	242	73.	24.2	1390.2
1	JAN	0125	43	1.	3.3	1382.1	1	JAN	0445	143	48.	16.1	1387.3	1	JAN	0805	243	73.	24.0	1390.2
1	JAN	0127	44	1.	3.3	1382.1	1	JAN	0447	144	49.	16.5	1387.4	1	JAN	0807	244	73.	23.9	1390.1
1	JAN	0129	45	1.	3.3	1382.1	1	JAN	0449	145	50.	16.5	1387.5	1	JAN	0809	245	72.	23.7	1390.1
1	JAN	0131	46	1.	3.3	1382.1	1	JAN	0451	146	51.	16.6	1387.6	1	JAN	0811	246	72.	23.5	1390.0
1	JAN	0133	47	1.	3.3	1382.1	1	JAN	0453	147	52.	16.7	1387.6	1	JAN	0813	247	72.	23.3	1389.9
1	JAN	0135	48	1.	3.3	1382.1	1	JAN	0455	148	52.	16.9	1387.7	1	JAN	0815	248	71.	23.2	1389.9
1	JAN	0137	49	1.	3.3	1382.1	1	JAN	0457	149	53.	17.0	1387.7	1	JAN	0817	249	71.	23.0	1389.8
1	JAN	0139	50	1.	3.3	1382.1	1	JAN	0459	150	53.	17.1	1387.7	1	JAN	0819	250	70.	22.8	1389.8
1	JAN	0141	51	1.	3.3	1382.1	1	JAN	0501	151	54.	17.1	1387.7	1	JAN	0821	251	70.	22.6	1389.7
1	JAN	0143	52	1.	3.3	1382.1	1	JAN	0503	152	54.	17.1	1387.7	1	JAN	0823	252	69.	22.5	1389.6
1	JAN	0145	53	1.	3.3	1382.1	1	JAN	0505	153	54.	17.2	1387.8	1	JAN	0825	253	69.	22.3	1389.6
1	JAN	0147	54	1.	3.3	1382.1	1	JAN	0507	154	54.	17.2	1387.8	1	JAN	0827	254	68.	22.1	1389.5
1	JAN	0149	55	1.	3.3	1382.1	1	JAN	0509	155	54.	17.2	1387.8	1	JAN	0829	255	68.	22.0	1389.5
1	JAN	0151	56	1.	3.3	1382.1	1	JAN	0511	156	54.	17.2	1387.8	1	JAN	0831	256	68.	21.8	1389.4
1	JAN	0153	57	1.	3.3	1382.1	1	JAN	0513	157	54.	17.2	1387.8	1	JAN	0833	257	67.	21.6	1389.3
1	JAN	0155	58	1.	3.3	1382.1	1	JAN	0515	158	54.	17.3	1387.8	1	JAN	0835	258	67.	21.5	1389.3
1	JAN	0157	59	1.	3.4	1382.1	1	JAN	0517	159	55.	17.5	1387.9	1	JAN	0837	259	66.	21.3	1389.2
1	JAN	0159	60	1.	3.4	1382.1	1	JAN	0519	160	57.	17.9	1388.0	1	JAN	0839	260	66.	21.1	1389.2
1	JAN	0201	61	1.	3.4	1382.1	1	JAN	0521	161	59.	18.6	1388.3	1	JAN	0841	261	65.	21.0	1389.1
1	JAN	0203	62	1.	3.4	1382.1	1	JAN	0523	162	61.	19.4	1388.6	1	JAN	0843	262	65.	20.8	1389.1
1	JAN	0205	63	1.	3.4	1382.1	1	JAN	0525	163	64.	20.3	1388.9	1	JAN	0845	263	64.	20.6	1389.0
1	JAN	0207	64	1.	3.4	1382.1	1	JAN	0527	164	66.	21.2	1389.2	1	JAN	0847	264	64.	20.5	1388.9
1	JAN	0209	65	1.	3.4	1382.1	1	JAN	0529	165	68.	22.0	1389.5	1	JAN	0849	265	64.	20.3	1388.9
1	JAN	0211	66	1.	3.4	1382.1	1	JAN	0531	166	70.	22.8	1389.7	1	JAN	0851	266	63.	20.1	1388.8
1	JAN	0213	67	1.	3.4	1382.1	1	JAN	0533	167	72.	23.1	1390.0	1	JAN	0853	267	63.	20.0	1388.8
1	JAN	0215	68	1.	3.4	1382.1	1	JAN	0535	168	73.	24.1	1390.2	1	JAN	0855	268	62.	19.8	1388.7
1	JAN	0217	69	1.	3.4	1382.1	1	JAN	0537	169	74.	24.6	1390.4	1	JAN	0857	269	62.	19.6	1388.6
1	JAN	0219	70	1.	3.4	1382.1	1	JAN	0539	170	75.	25.2	1390.5							

+		RCP21	398.	5.20	58.	35.	35.	1.83		
+									1.77	5.20
+	HYDROGRAPH AT	S2A2	32.	4.30	7.	4.	4.	.04		
+	2 COMBINED AT	CF2A2	408.	5.20	64.	39.	39.	1.87		
+	ROUTED TO	RCP22	403.	5.23	64.	39.	39.	1.87		
+									2.18	5.23
+	HYDROGRAPH AT	S2B	36.	4.07	4.	3.	3.	.03		
+	2 COMBINED AT	CF2B	404.	5.23	69.	42.	42.	1.89		
+	ROUTED TO	RCP2B	394.	5.27	69.	42.	42.	1.89		
+									1.22	5.27
+	HYDROGRAPH AT	S2C	37.	4.07	5.	3.	3.	.03		
+	2 COMBINED AT	CF2C	395.	5.27	73.	45.	45.	1.92		
+	ROUTED TO	RCP2C	392.	5.30	73.	45.	45.	1.92		
+									1.62	5.30
+	HYDROGRAPH AT	S2D	28.	4.10	4.	2.	2.	.02		
+	HYDROGRAPH AT	S2I	38.	4.07	5.	3.	3.	.03		
+	3 COMBINED AT	CP2DI	394.	5.30	82.	50.	50.	1.97		
+	ROUTED TO	RCPDI	379.	5.40	82.	50.	50.	1.97		
+									1.54	5.40
+	HYDROGRAPH AT	S2E	32.	4.17	6.	3.	3.	.03		
+	2 COMBINED AT	CF2E	383.	5.40	87.	53.	53.	2.01		
+	ROUTED TO	BSN-A	82.	6.43	64.	39.	39.	2.01		
+									1391.86	6.43
+	DIVERSION TO	DVRT1	82.	.03	64.	39.	39.	2.01		
+	HYDROGRAPH AT	SPILL1	0.	.03	0.	0.	0.	2.01		

*** NORMAL END OF HEC-1 ***


-----DSS---ZCLOSE Unit: 71, File: TTM-100.DSS
 Pointer Utilization: .25
 Number of Records: 2
 File Size: 16.9 Kbytes
 Percent Inactive: .00

Curve Plotted Curves for Rectangular Channel

Project Description	
Project File	c:\atumwsh\dgn\project1.fm2
Worksheet	Basin Spillway Inlet Channel
Flow Element	Rectangular Channel
Method	Manning's Formula
Solve For	Channel Depth

Constant Data	
Mannings Coefficient	0.018
Bottom Width	65.00 ft


Input Data			
	Minimum	Maximum	Increment
Discharge	450.00	1,000.00	50.00 cfs
Channel Slope	0.000100	0.001000	0.000200 ft/ft



Cross Section
Cross Section for Rectangular Channel

Project Description	
Project File	c:\atumwsh\dgn\project1.fm2
Worksheet	Basin Spillway Inlet Channel
Flow Element	Rectangular Channel
Method	Manning's Formula
Solve For	Channel Depth

Section Data	
Mannings Coefficient	0.018
Channel Slope	0.000100 ft/ft
Depth	3.74 ft
Bottom Width	65.00 ft
Discharge	450.00 cfs






Figure 243. Basic proportions of a baffled chute spillway. 288-D-2807.

baffles should be buried as needed to protect against degradation.

- (10) The chute training walls should be three times as high as the baffle piers measured normal to the floor. This wall height will contain the main flow

and most of the splash. It is not necessary or practical to build the walls high enough to contain all the splash.

- (11) Riprap should be placed at the downstream ends of the training walls to prevent erosion of the banks.





Figure 244. Recommended baffle pier heights and allowable velocities for baffled chute spillways. 288-D-2806.




Figure 242. Bafled apron drop spillway used at Conconully Dam in Washington. The flow shown passing over the spillway is about 50 cfs. P21-141-178NA.

- (1) Determine the maximum expected discharge, Q .
- (2) Determine unit design discharge $q=Q/W$, where W is the chute width. The chute width may depend on the upstream channel width, the downstream channel width, economy, topography, and frequency of discharge, as well as maximum discharge.
- (3) Entrance velocity, V , should be as low as practical. Ideal conditions exist when $V_1=\sqrt[3]{gq}-5$, curve D, figure 244, for discharges up to 69 second-feet per foot of width. Velocities near critical, $V_c=\sqrt[3]{gq}$, curve C, figure 244, or above cause the flow to be thrown into the air after striking the first baffle pier. High velocities may cause the flow to pass completely over the next row or two of baffle piers. It is very important that proper flow conditions be provided at the entrance to the baffle apron because satisfactory performance of the entire structure may hinge on proper entrance flow conditions.
- (4) A vertical offset between the approach channel floor and the chute is used to form a desirable uniform entrance velocity, V_1 , and will vary in individual installations. A short radius curve provides a crest on the sloping chute. The first row of baffle piers should be placed no more than 12 inches in elevation below the crest. Alternate rows should be staggered to provide a baffle pier below each space and a space below each baffle pier.
- (5) The baffle pier height, H , should be about $0.8 D_c$ or $0.9 D_c$, where the critical depth (D_c) for the rectangular chute is given by the formula $D_c=\sqrt[3]{q^2/g}$ and is shown by curve A of figure 244. Baffle pier height is not a critical dimension but should not be less than recommended.
- (6) Baffle pier widths and spaces should be equal, preferably about one and one-half H , but not less than H . Other baffle pier dimensions are not critical hydraulically. Suggested cross sectional dimensions are given.
- (7) Row spacing of baffle piers along the chute slope should be H divided by the slope, where the slope is given in decimal form. A 2:1 slope, 0.50 in decimal form, makes the row spacing equal to $2H$ parallel to the chute floor.
- (8) The baffle piers are usually constructed with the upstream face normal to the chute floor surface; however, piers with vertical faces may be used. Vertical face piers tend to produce more splash and less bed scour, but the differences are minor.
- (9) Four rows of baffle piers are needed to establish full control of the flow, although fewer rows have operated successfully. As many additional rows as required beyond the fourth maintain the control established upstream. At least one row of baffles should be buried below the outlet channel grade to protect against scour. Additional rows of


Tatum Wash Sedimentation Basin Plan: Plan 02 5/14/1997
Most Upstream XS Riv Sta = 10




Tatum Wash Sedimentation Basin Plan: Plan 02 5/14/1997
Riv Sta = 8



Tatum Wash Sedimentation Basin Plan: Plan 02 5/14/1997
Riv Sta = 6



Tatum Wash Sedimentation Basin Plan: Plan 02 5/14/1997
Riv Sta = 5



HEC-RAS Plan: Plan 02 Reach: Tatum Wash 5/14/1997

River Sta.	E.G. Elev (ft)	W.S. Elev (ft)	Vel Head (ft)	Prctn Loss (ft)	C & E Loss (ft)	Q Left (cfs)	Q Channel (cfs)	Q Right (cfs)	Top Width (ft)
10	1401.91	1401.73	0.18	0.14	0.01		600.00		79.34
10	1402.21	1402.02	0.19	0.14	0.01		700.00		81.62
10	1402.50	1402.30	0.20	0.13	0.01		800.00		83.80
10	1403.04	1402.82	0.21	0.12	0.02		1000.00		87.86
10	1405.78	1405.48	0.30	0.09	0.01		2300.00		99.00
8	1401.75	1401.62	0.13	0.10	0.01		600.00		85.58
8	1402.06	1401.92	0.14	0.10	0.01		700.00		88.09
8	1402.35	1402.21	0.15	0.09	0.01		800.00		90.45
8	1402.90	1402.74	0.16	0.09	0.01		1000.00		94.85
8	1405.68	1405.43	0.25	0.07	0.01		2300.00		99.00
6	1401.64	1401.54	0.10	0.03	0.01		600.00		88.77
6	1401.95	1401.84	0.11	0.03	0.01		700.00		91.16
6	1402.25	1402.13	0.12	0.03	0.01		800.00		93.41
6	1402.81	1402.67	0.14	0.03	0.01		1000.00		96.90
6	1405.60	1405.38	0.22	0.03	0.01		2300.00		100.00
5	1401.60	1401.53	0.07	0.00	0.00		600.00		94.47
5	1401.91	1401.84	0.08	0.00	0.00		700.00		95.63
5	1402.21	1402.13	0.09	0.00	0.00		800.00		96.72
5	1402.77	1402.67	0.10	0.00	0.00		1000.00		98.75
5	1405.56	1405.37	0.19	0.00	0.00		2300.00		100.00

HEC-RAS Plan: Plan 02 Reach: Tatum Wash 5/14/1997

River Sta.	Q Total (cfs)	Min Ch El (ft)	W.S. Elev (ft)	Ch W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/m)	Vel Cbl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Friction Coef
10	600.00	1398.00	1401.73	1400.58	1401.91	0.003573	3.37	178.14	79.34	0.40
10	700.00	1398.00	1402.02	1400.73	1402.21	0.003335	3.47	201.82	81.62	0.39
10	800.00	1398.00	1402.30	1400.87	1402.50	0.003145	3.56	224.93	83.80	0.38
10	1000.00	1398.00	1402.82	1401.13	1403.04	0.002862	3.71	269.72	87.86	0.37
10	2300.00	1398.00	1405.48	1402.47	1405.78	0.002006	4.39	524.41	99.00	0.34
2	600.00	1398.00	1401.62	1400.20	1401.75	0.002399	2.90	206.89	85.58	0.33
2	700.00	1398.00	1401.92	1400.34	1402.06	0.002277	3.00	233.25	88.09	0.33
2	800.00	1398.00	1402.21	1400.48	1402.35	0.002178	3.09	258.88	90.45	0.32
2	1000.00	1398.00	1402.74	1400.73	1402.90	0.002028	3.24	308.30	94.85	0.32
2	2300.00	1398.00	1405.43	1402.04	1405.68	0.001524	4.01	573.04	99.00	0.29
6	600.00	1398.00	1401.54	1399.84	1401.64	0.001694	2.57	233.12	88.77	0.28
6	700.00	1398.00	1401.84	1399.99	1401.95	0.001645	2.68	260.80	91.16	0.28
6	800.00	1398.00	1402.13	1400.13	1402.25	0.001603	2.78	287.60	93.41	0.28
6	1000.00	1398.00	1402.67	1400.37	1402.81	0.001526	2.95	339.01	96.90	0.28
6	2300.00	1398.00	1405.38	1401.67	1405.60	0.001274	3.78	608.22	100.00	0.27
5	600.00	1398.00	1401.53	1399.49	1401.60	0.001001	2.12	282.98	94.47	0.22
5	700.00	1398.00	1401.84	1399.62	1401.91	0.001000	2.24	312.33	95.63	0.22
5	800.00	1398.00	1402.13	1399.74	1402.21	0.001000	2.35	340.33	96.72	0.22
5	1000.00	1398.00	1402.67	1399.97	1402.77	0.001001	2.54	393.07	98.75	0.22
5	2300.00	1398.00	1405.37	1401.16	1405.56	0.001000	3.47	663.66	100.00	0.24

Baffle Drop

Ref. Design of Small Dams , Bureau of Reclamation, Second Ed 1973


Discharge, Q (cfs)	450	600	800	1000	2000
Chute Width, W (ft)	65	65	65	65	65
Unit Discharge, q (cfs/ft)	6.92	9.23	12.31	15.38	35.38
Spillway height, Hs (ft)	14	14	14	14	14
Spillway Slope, Z:1	3.2	3.2	3.2	3.2	3.2
Entrance Velocity, V1 (fps) From HEC - 2 Run	2.38	2.57	2.78	2.95	3.78
Ideal Velocity, $V_i=(qg)^{1/3-5}$	1.06	1.67	2.35	2.91	5.44
Critical Velocity, $V_c=(qg)^{1/3}$	6.06	6.67	7.35	7.91	10.44
Critical Depth, $D_c=(q^2/g)^{1/3}$	1.14	1.38	1.68	1.94	3.39
Baffle Height, H (ft)	0.91	1.11	1.34	1.56	2.71
Baffle Width, Wb (ft), 1.5H	1.37	1.66	2.01	2.33	4.07
Baffle Row Spacing, 2H	1.83	2.21	2.68	3.11	5.42
Number of Baffles per row	24	20	16	14	8
Number of rows	43	43	44	44	44
Wall Height, Hw (ft), 3H	2.74	3.32	4.02	4.67	8.13

Curve Plotted Curves for Rectangular Channel

Project Description	
Project File	c:\atumwsh\dgn\project1.fm2
Worksheet	Basin Spillway Inlet Channel
Flow Element	Rectangular Channel
Method	Manning's Formula
Solve For	Channel Depth

Constant Data	
Mannings Coefficient	0.018
Bottom Width	65.00 ft


Input Data			
	Minimum	Maximum	Increment
Discharge	450.00	1,000.00	50.00 cfs
Channel Slope	0.000100	0.001000	0.000200 ft/ft



Cross Section
Cross Section for Rectangular Channel

Project Description	
Project File	c:\atumwsh\dgn\project1.fm2
Worksheet	Basin Spillway Inlet Channel
Flow Element	Rectangular Channel
Method	Manning's Formula
Solve For	Channel Depth

Section Data		
Mannings Coefficient	0.018	
Channel Slope	0.000100	ft/ft
Depth	3.74	ft
Bottom Width	65.00	ft
Discharge	450.00	cfs






Figure 243. Basic proportions of a baffled chute spillway. 288-D-2807.

baffles should be buried as needed to protect against degradation.

- (10) The chute training walls should be three times as high as the baffle piers measured normal to the floor. This wall height will contain the main flow

and most of the splash. It is not necessary or practical to build the walls high enough to contain all the splash.

- (11) Riprap should be placed at the downstream ends of the training walls to prevent erosion of the banks.





Figure 244. Recommended baffle pier heights and allowable velocities for baffled chute spillways. 288-D-2806.




Figure 242. Baffled apron drop spillway used at Conconully Dam in Washington. The flow shown passing over the spillway is about 50 cfs. P21-141-178NA.

- (1) Determine the maximum expected discharge, Q .
- (2) Determine unit design discharge $q=Q/W$, where W is the chute width. The chute width may depend on the upstream channel width, the downstream channel width, economy, topography, and frequency of discharge, as well as maximum discharge.
- (3) Entrance velocity, V , should be as low as practical. Ideal conditions exist when $V_1=\sqrt[3]{gq}-5$, curve D, figure 244, for discharges up to 69 second-feet per foot of width. Velocities near critical, $V_c=\sqrt[3]{gq}$, curve C, figure 244, or above cause the flow to be thrown into the air after striking the first baffle pier. High velocities may cause the flow to pass completely over the next row or two of baffle piers. It is very important that proper flow conditions be provided at the entrance to the baffle apron because satisfactory performance of the entire structure may hinge on proper entrance flow conditions.
- (4) A vertical offset between the approach channel floor and the chute is used to form a desirable uniform entrance velocity, V_1 , and will vary in individual installations. A short radius curve provides a crest on the sloping chute. The first row of baffle piers should be placed no more than 12 inches in elevation below the crest. Alternate rows should be staggered to provide a baffle pier below each space and a space below each baffle pier.
- (5) The baffle pier height, H , should be about $0.8 D_c$ or $0.9 D_c$, where the critical depth (D_c) for the rectangular chute is given by the formula $D_c=\sqrt[3]{q^2/g}$ and is shown by curve A of figure 244. Baffle pier height is not a critical dimension but should not be less than recommended.
- (6) Baffle pier widths and spaces should be equal, preferably about one and one-half H , but not less than H . Other baffle pier dimensions are not critical hydraulically. Suggested cross sectional dimensions are given.
- (7) Row spacing of baffle piers along the chute slope should be H divided by the slope, where the slope is given in decimal form. A 2:1 slope, 0.50 in decimal form, makes the row spacing equal to $2H$ parallel to the chute floor.
- (8) The baffle piers are usually constructed with the upstream face normal to the chute floor surface; however, piers with vertical faces may be used. Vertical face piers tend to produce more splash and less bed scour, but the differences are minor.
- (9) Four rows of baffle piers are needed to establish full control of the flow, although fewer rows have operated successfully. As many additional rows as required beyond the fourth maintain the control established upstream. At least one row of baffles should be buried below the outlet channel grade to protect against scour. Additional rows of


Tatum Wash Sedimentation Basin Plan: Plan 02 5/14/1997
 Most Upstream XS Riv Sta = 10




Tatum Wash Sedimentation Basin Plan: Plan 02 5/14/1997
Riv Sta = 8



Tatum Wash Sedimentation Basin Plan: Plan 02 5/14/1997
Riv Sta = 6



Tatum Wash Sedimentation Basin Plan: Plan 02 5/14/1997
Riv Sta = 5




HEC-RAS Plan: Plan 02 Reach: Tatum Wash 5/14/1997

River Sta.	E.G. Elev (ft)	W.S. Elev (ft)	Vel Head (ft)	Frctn Loss (ft)	C. & E Loss (ft)	Q Left (cfs)	Q Channel (cfs)	Q Right (cfs)	Top Width (ft)
10	1401.91	1401.73	0.18	0.14	0.01		600.00		79.34
10	1402.21	1402.02	0.19	0.14	0.01		700.00		81.62
10	1402.50	1402.30	0.20	0.13	0.01		800.00		83.80
10	1403.04	1402.82	0.21	0.12	0.02		1000.00		87.86
10	1405.78	1405.48	0.30	0.09	0.01		2300.00		99.00
8	1401.75	1401.62	0.13	0.10	0.01		600.00		85.58
8	1402.06	1401.92	0.14	0.10	0.01		700.00		88.09
8	1402.35	1402.21	0.15	0.09	0.01		800.00		90.45
8	1402.90	1402.74	0.16	0.09	0.01		1000.00		94.85
8	1405.68	1405.43	0.25	0.07	0.01		2300.00		99.00
6	1401.64	1401.54	0.10	0.03	0.01		600.00		88.77
6	1401.95	1401.84	0.11	0.03	0.01		700.00		91.16
6	1402.25	1402.13	0.12	0.03	0.01		800.00		93.41
6	1402.81	1402.67	0.14	0.03	0.01		1000.00		96.90
6	1405.60	1405.38	0.22	0.03	0.01		2300.00		100.00
5	1401.60	1401.53	0.07	0.00	0.00		600.00		94.47
5	1401.91	1401.84	0.08	0.00	0.00		700.00		95.63
5	1402.21	1402.13	0.09	0.00	0.00		800.00		96.72
5	1402.77	1402.67	0.10	0.00	0.00		1000.00		98.75
5	1405.56	1405.37	0.19	0.00	0.00		2300.00		100.00

HEC-RAS Plan: Plan 02 Reach: Tatum Wash 5/14/1997

River Sta.	Q Total (cfs)	Min Chl El. (ft)	M.S. Elev (ft)	Ch.W.S. (ft)	E.G. Elev (ft)	E.G. Slope (ft/ft)	Vel Chnl (ft/s)	Flow Area (sq ft)	Top Width (ft)	Fradee # Chl
10	600.00	1398.00	1401.73	1400.58	1401.91	0.003573	3.37	178.14	79.34	0.40
10	700.00	1398.00	1402.02	1400.73	1402.21	0.003335	3.47	201.82	81.62	0.39
10	800.00	1398.00	1402.30	1400.87	1402.50	0.003145	3.56	224.93	83.80	0.38
10	1000.00	1398.00	1402.82	1401.13	1403.04	0.002862	3.71	269.72	87.86	0.37
10	2300.00	1398.00	1405.48	1402.47	1405.78	0.002006	4.39	524.41	99.00	0.34
8	600.00	1398.00	1401.62	1400.20	1401.75	0.002399	2.90	206.89	85.58	0.33
8	700.00	1398.00	1401.92	1400.34	1402.06	0.002277	3.00	233.25	88.09	0.33
8	800.00	1398.00	1402.21	1400.48	1402.35	0.002178	3.09	258.88	90.45	0.32
8	1000.00	1398.00	1402.74	1400.73	1402.90	0.002028	3.24	308.30	94.85	0.32
8	2300.00	1398.00	1405.43	1402.04	1405.68	0.001524	4.01	573.04	99.00	0.29
6	600.00	1398.00	1401.54	1399.84	1401.64	0.001694	2.57	233.12	88.77	0.28
6	700.00	1398.00	1401.84	1399.99	1401.95	0.001645	2.68	260.80	91.16	0.28
6	800.00	1398.00	1402.13	1400.13	1402.25	0.001603	2.78	287.60	93.41	0.28
6	1000.00	1398.00	1402.67	1400.37	1402.81	0.001526	2.95	339.01	96.90	0.28
6	2300.00	1398.00	1405.38	1401.67	1405.60	0.001274	3.78	608.22	100.00	0.27
5	600.00	1398.00	1401.53	1399.49	1401.60	0.001001	2.12	282.98	94.47	0.22
5	700.00	1398.00	1401.84	1399.62	1401.91	0.001000	2.24	312.33	95.63	0.22
5	800.00	1398.00	1402.13	1399.74	1402.21	0.001000	2.35	340.33	96.72	0.22
5	1000.00	1398.00	1402.67	1399.97	1402.77	0.001001	2.54	393.07	98.75	0.22
5	2300.00	1398.00	1405.37	1401.16	1405.56	0.001000	3.47	663.66	100.00	0.24



Tatum Wash Detention Basin Outlet

Basin Outlet works that flow into 78" S.D. The assumption is that a maximum of 100 cfs can enter the SD after all events to drain the basin. The outlet structure will be outfitted with backflow preventers on all orifices entering the structure to keep the SD from outleting into the basin. All flows in excess of 1394 will spill into Shea Blvd.

Top of Basin 1394 Coefficient of discharge for square opening 0.59
 Bottom of Basin 1380.5 $Q_o = C_a(2gh)^{.5}$ $Q_w = CLH^{3/2}$

	Outlet A		Outlet B		Outlet Spill		Emergency Spillway		Outlet into 78" SD			
Dia. of orifice (ft)	2		2		Length = 20		Length = 48		3.5			
Invert of orifice	1381		1385		Coefficient 3.1		Coefficient 2.63		1381			
Center of orifice	1382		1386		Elevation 1392		Elevation = 1393		1382.8			
Area of orifice (sf)	3.14		3.14									
Water Elevation	Available Head (ft)	Discharge (cfs)	Total Discharge (cfs)	HW/D	*Discharge (cfs)	Storage Ac-Ft						
1382	0	0.0	0	0.0	0	0.0	0	0.0	0	0.29		3.11
1383	1	14.9	0	0.0	0	0.0	0	0.0	15	0.57	22	
1384	2	21.0	0	0.0	0	0.0	0	0.0	21	0.86	40	7.59
1385	3	25.8	0	0.0	0	0.0	0	0.0	26	1.14	60	
1386	4	29.7	0	0.0	0	0.0	0	0.0	30	1.43	75	12.46
1387	5	33.2	1	14.9	0	0.0	0	0.0	48	1.71	90	
1388	6	36.4	2	21.0	0	0.0	0	0.0	57	2.00	100	17.72
1389	7	39.3	3	25.8	0	0.0	0	0.0	65	2.29	110	
1390	8	42.1	4	29.7	0	0.0	0	0.0	72	2.57	120	23.40
1391	9	44.6	5	33.2	0	0.0	0	0.0	78	2.86	130	
1392	10	47.0	6	36.4	0	0.0	0	0.0	83	3.14	140	29.50
1393	11	49.3	7	39.3	1	62.0	0	0.0	151	3.43	148	32.71
1394	12	51.5	8	42.1	2	175.4	1	126.2	395	3.71	155	36.03

* Discharge based upon Inlet Control nomographs from HEC 5(zero velocity head)

DESIGN COMPUTATIONS

PROJECT _____

Sta 99+30± 1 year - area 18 - Q = 48 cfs.
2 year " " Q = 81 cfs.

Storm Drain Sized for 60 to 70 cfs.

use 48 cfs.

Weir - $Q = 2.67 L H^{3/2}$

H = 1' L req = $48 \div 2.67 = 18'$
 H = 1.1' L " = $48 \div (2.67 \times 1.1537) = 15.6'$
 H = 1.25' L " = $48 \div (2.67 \times 1.3975) = 12.9'$
 H = 1.5' L " = $48 \div (2.67 \times 1.8371) = 9.8'$

COPY

C-14.03 for Double 42" pipe 10'-6" + 2(2'-3") = 15' wide.
 effective weir = 15' - 2'-9" = 12'-3"
 Modify to 18'-20' wide 18' h = 1.1' 20' h = 1' use 18'

Q = 12 cfs H = 1' L req = $12 \div 2.67 = 4.5'$

C-14.03 for 30" 3'-6" + 2(1'-6") = 6'-6"
 effective weir = 6'-6" - 2'-0" = 4'-6" OK use

Box 7'-6" x 3'

Size Pipe - DCB criteria -

Try 18" pipe. $DCB = \frac{1.5V^4}{29} + d + 0.5 = 18" V = 6.78 DCB = 3.07$
 $+ \frac{2}{5.07}$

BK S/w = 92.28

Top. wall 92.78

Lip 90.78 W.S = 91.78 (0.5' below s/w)

18" 87.71

$\frac{92.78}{3.37} = 27.53$

USE	For Q = 48 cfs	36"	$1.07 + 2 + 1.5 = 4.57$	6'-5" deep 5.5 to 6'
	→ 24 cfs	30"	$DCB = 2.22 + 2.5 + 1.5 = 5.22$	Below Lip 3' Deep.
	"	24"	$= 1.36 + 2 + 1.5 = 3.86$	Below Lip 6' Deep. 5'-6" 3'
	"	18"	$4.28 + 1.5 + 1.5 = 6.28$	

Eq 36" 43x27 A = 6.4 $1.71 + 2.25 + 1.5 = 4.06$ 6' Deep.

Eq 24" 29x18 " 2.8 $1.71 + 1.5 + 1.5 = 3.71$ 6' Deep.

use Double 24" Better inlet conditions with 13/16" Back wall.

Box 4'-10" x (4'-6" to 19)

15" 1.24
18" 1.77
24" 3.14
30" 4.91
36" 7.07

----- Beginning Calculation Cycle -----

Discharge: 440.00 cfs at node I-42
 Discharge: 440.00 cfs at node MH6
 Discharge: 520.00 cfs at node Basin Outlet
 Discharge: 520.00 cfs at node MH #7
 Discharge: 520.00 cfs at node MH8
 Discharge: 520.00 cfs at node MH9
 Discharge: 520.00 cfs at node MH10
 Discharge: 520.00 cfs at node MH11
 Discharge: 520.00 cfs at node MH12
 Discharge: 520.00 cfs at node MH13
 Discharge: 520.00 cfs at node Outlet
 Beginning iteration 1
 Discharge: 440.00 cfs at node I-42
 Discharge: 440.00 cfs at node MH6
 Discharge: 520.00 cfs at node Basin Outlet
 Discharge: 520.00 cfs at node MH #7
 Discharge: 520.00 cfs at node MH8
 Discharge: 520.00 cfs at node MH9
 Discharge: 520.00 cfs at node MH10
 Discharge: 520.00 cfs at node MH11
 Discharge: 520.00 cfs at node MH12
 Discharge: 520.00 cfs at node MH13
 Discharge: 520.00 cfs at node Outlet
 Discharge Convergence Achieved in 1 iterations: relative error: 0.0
 Warning: No Duration data exists in IDF Table
 Information: Outlet Known flow propagated from upstream junctions.
 Information: MH13 Known flow propagated from upstream junctions.
 Information: P2 Surcharged condition
 Information: MH12 Known flow propagated from upstream junctions.
 Information: P3 Surcharged condition
 Information: MH11 Known flow propagated from upstream junctions.
 Information: P4 Surcharged condition
 Information: MH10 Known flow propagated from upstream junctions.
 Information: P5 Surcharged condition
 Information: MH9 Known flow propagated from upstream junctions.
 Information: P6 Surcharged condition
 Information: MH8 Known flow propagated from upstream junctions.
 Information: P7 Surcharged condition
 Information: MH #7 Known flow propagated from upstream junctions.
 Information: P8 Surcharged condition
 Information: P9 Surcharged condition
 Information: MH6 Known flow propagated from upstream junctions.
 Information: P10 Surcharged condition

----- Calculations Complete -----

** Analysis Options **

Friction method: Manning's Formula
 HGL Convergence Test: 0.001000
 Maximum Network Traversals: 20
 Number of Flow Profile Steps: 10
 Discharge Convergence Test: 0.001000
 Maximum Design Passes: 3

----- Network Quick View -----

Label	Length	Size	Discharge	Hydraulic Grade	
				Upstream	Downstream
P9	182.00	78 inch	440.00	1,393.78	1,392.50
P3	268.00	84 inch	520.00	1,364.88	1,363.10
P1	633.00	84 inch	520.00	1,358.87	1,354.27
P2	638.00	84 inch	520.00	1,363.10	1,358.87
P4	642.00	84 inch	520.00	1,369.13	1,364.88
P6	634.00	78 inch	520.00	1,382.17	1,375.93
P8	410.00	78 inch	520.00	1,392.50	1,388.47
P7	640.00	78 inch	520.00	1,388.47	1,382.17
P5	691.00	78 inch	520.00	1,375.93	1,369.13

Project Title: Tatum Wash Detention Basin

c:\haestad\strnc\final.strn

07/22/97 12:49:23 PM

Maricopa County

© Haestad Methods, Inc. 37 Brookside Road Waterbury, CT 06708 USA (203) 755-1666

Project Engineer: Michael A. Lopez


StormCAD v1.0

Page 1 of 2

P10 10.00 78 inch 440.00 1,393.85 1,393.78

Label	Discharge	Elevations		
		Ground	Upstream HGL	Downstream HGL
Outlet	520.00	1,356.50	1,354.27	1,354.27
MH11	520.00	1,368.20	1,364.88	1,364.88
MH9	520.00	1,380.00	1,375.93	1,375.93
Basin Out	520.00	1,393.00	1,392.50	1,392.50
MH6	440.00	1,396.00	1,393.78	1,393.78
MH #7	520.00	1,391.60	1,388.47	1,388.47
MH8	520.00	1,385.60	1,382.17	1,382.17
MH12	520.00	1,366.00	1,363.10	1,363.10
MH13	520.00	1,362.00	1,358.87	1,358.87
MH10	520.00	1,374.00	1,369.13	1,369.13
I-42	440.00	1,396.00	1,393.85	1,393.85

Elapsed: 0 minute(s) 2 second(s)



Hydraulic Grade Line Report W/O Basin Flows

----- Calculations Complete -----

**** Analysis Options ****

Friction method: Manning's Formula
 HGL Convergence Test: 0.001000
 Maximum Network Traversals: 20
 Number of Flow Profile Steps: 10
 Discharge Convergence Test: 0.001000
 Maximum Design Passes: 3

----- Network Quick View -----

Label	Length	Size	Discharge	Hydraulic Grade	
				Upstream	Downstream
P9	182.00	78 inch	440.00	1,388.12	1,386.38
P3	268.00	84 inch	440.00	1,361.79	1,360.26
P1	633.00	84 inch	440.00	1,357.10	1,353.85
P2	638.00	84 inch	440.00	1,360.26	1,357.10
P4	642.00	84 inch	440.00	1,366.14	1,361.79
P6	634.00	78 inch	440.00	1,377.73	1,372.56
P8	410.00	78 inch	440.00	1,386.38	1,383.09
P7	640.00	78 inch	440.00	1,383.09	1,377.73
P5	691.00	78 inch	440.00	1,372.56	1,365.99
P10	10.00	78 inch	440.00	1,388.56	1,388.12

Label	Discharge	Ground	Elevations	
			Upstream HGL	Downstream HGL
Outlet	440.00	1,356.50	1,353.85	1,353.85
MH11	440.00	1,368.20	1,361.79	1,361.79
MH9	440.00	1,380.00	1,372.56	1,372.56
Basin Out	440.00	1,393.00	1,386.38*	1,386.38 *
MH6	440.00	1,396.00	1,388.12	1,388.12
MH #7	440.00	1,391.60	1,383.09	1,383.09
MH8	440.00	1,385.60	1,377.73	1,377.73
MH12	440.00	1,366.00	1,360.26	1,360.26
MH13	440.00	1,362.00	1,357.10	1,357.10
MH10	440.00	1,374.00	1,366.14	1,366.14
I-42	440.00	1,396.00	1,388.56	1,388.56

Elapsed: 0 minute(s) 3 second(s)

* HGL was adjusted for datum difference (lowered .8 ft) and used for outlet analysis.

Principal Outlet Capacity with Tailwater

H = HWE - TWE
 V=velocity, fps
 g = gravity = 32.2
 Ke=entrance loss = 0.5
 n = friction coefficient = 0.013
 D = diameter culvert (in) = 42
 L =culvert length = 94
 R =hydraulic radius , ft = 0.875
 TWE = tailwater elevation = 1385.6
 HWE = headwater elevation

$$V = (H / [(1 + K_e / 2g) + (n^2 L / 2.21 R^{4/3})])$$

1+Ke/2g = 1.008
 n²L = 0.016
 2.21R^{4/3} = 1.850

HWE	H	V	Q
Elevation			
1382	0	0.00	0.0
1383	0	0.00	0.0
1384	0	0.00	0.0
1385	0	0.00	0.0
1386	0.4	0.39	3.8
1387	1.4	1.38	13.2
1388	2.4	2.36	22.7
1389	3.4	3.35	32.2
1390	4.4	4.33	41.6
1391	5.4	5.31	51.1
1392	6.4	6.30	60.6
1393	7.4	7.28	70.0
1394	8.4	8.26	79.5

Table
Rating Table for Circular Channel

Project Description	
Project File	c:\haestad\fmw\project1.fm2
Worksheet	Tatum Wash Outlet Pipe
Flow Element	Circular Channel
Method	Manning's Formula
Solve For	Discharge


Constant Data	
Mannings Coefficient	0.013
Channel Slope	0.002294 ft/ft
Diameter	42.00 in

Input Data			
	Minimum	Maximum	Increment
Depth	0.50	3.50	0.50 ft

Rating Table		
Depth (ft)	Discharge (cfs)	Velocity (ft/s)

0.50	2.12	2.51
1.00	8.58	3.78
1.50	18.40	4.67
2.00	30.00	5.28
2.50	41.41	5.63
3.00	49.95	5.69
3.50	48.19	5.01

*Meets & exceeds minimum
Velocity as stipulated in
Drainage Design Manual (4.2.2.2)*



**FLOOD CONTROL DISTRICT OF MARICOPA COUNTY
CONTRACT FCD 97-22
TATUM WASH DETENTION BASIN NO. 1**

SPECIAL PROVISIONS

SECTION 201 - CLEARING AND GRUBBING

Clearing and grubbing shall conform to Section 201 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 201.1 - Description

Add the following to this subsection:

The Contractor shall protect-in-place all of the perimeter masonry walls and footers during this operation.

Subsection 201.5 - Payment

Replace this subsection with the following:

The project construction limits shall be cleared of all trees, vegetation, trash and debris. Such material as collected shall be disposed of at an approved landfill site and shall be subject to landfill fees so assessed, which will be included in the unit price bid for this item. Weigh tickets from all landfill disposal must be furnished to the Engineer.

Payment for clearing and grubbing as such will be paid for at the lump sum price bid for, and shall be full compensation for all labor, equipment, disposing of refuse and all other items that are incidental or appurtenant.

ITEM 201 - CLEARING AND GRUBBING

Subsection 201.6 - Measurement, Removal, and Disposal of Trees:

Replace this subsection with the following:

No measurement shall be made for the removal and disposal of trees.

Subsection 201.7 - Payment, Removal, and Disposal of Trees:

Replace this subsection with the following:

No payment shall be made for the removal and disposal of trees as such; the cost thereof shall be included in the price of clearing and grubbing.

SECTION 202 - MOBILIZATION

Add this section to the MAG Uniform Standard Specifications

Subsection 202.1 - Description

The work under this section shall consist of preparatory work and operations, including but not limited to, the movement of personnel, equipment, supplies and incidentals to the project site; the establishment of all offices, buildings and other facilities necessary for work on the project, and for all other work and operations that must be performed and costs incurred prior to beginning work on various items on the project site.

Field Office:

No field office will be required for this project.

Subsection 202.1 - Payment

Payment shall be made on the basis of the lump sum price bid and shall be full compensation for supplying and furnishing all materials, facilities, and services and performing all work involved as specified herein. The lump sum price bid shall not exceed three (3%) percent of the total project bid amount exclusive of mobilization.

ITEM 202 -1 - MOBILIZATION

SECTION 206 - STRUCTURE EXCAVATION AND BACKFILL

Structure excavation and backfill shall conform to Section 206 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 206.2 - Foundation Material Treatment

Add the following:

Foundation bearing surfaces shall be free of debris and water softened materials prior to placing concrete and reinforcing steel. Any loose or disturbed zones should be removed and replaced with compacted fill or lean concrete.

Subsection 206.4 - Structure Backfill

Add the following:

Compaction of structure backfill soils against embedded footings, walls, and headwall structures shall be accomplished to a minimum 95 percent of the maximum ASTM D698 density.

Compaction against wing walls, or channel lining within 3 feet of the walls or lining shall be accomplished using non-wheeled, hand operated compaction equipment only.

Backfill behind subsurface walls designed to support utilities, pavement, channels, or other facilities should be compacted to density criteria from Section 211. Backfills shall consist of free draining granular soils which exhibit low expansive potentials. The material shall be free of vegetation, debris, organic contaminants, and fragments larger than 6 inches in size.

Compaction operations shall be accomplished by mechanical methods. Water settling or jetting shall not be permitted.

On-site soils may be used in structural fills or backfills except for high plasticity on-site soils (P.I. > 12) which may not be used in structure fills or backfills. Imported soil used for fills under pavements, or channels, backfills around structures should be granular soils conforming to the following requirements:

Sieve Size	Percent Passing
3"	100
3/4"	60-80
#8	35-80
#200	0-12

(Arizona Test Method 201)

Note: Maximum size may be reduced at the Engineer's direction to satisfy trenching and landscape requirements, etc.

Subsection 206.5 - Payment

Replace this subsection with the following:

No payment will be made for structure excavation and backfill as such; the cost thereof shall be included in the bid price for the construction or installation of the items to which such excavation and backfill is incidental or appurtenant.

SECTION 211 - FILL CONSTRUCTION

Fill construction shall conform to Section 211 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 211.1 - Description

Add the following:

Work under this item shall consist of filling to raise the grade for the maintenance access road around the perimeter of the detention basin and to fill low areas along both sides of the inlet spillway structure.

Subsection 211.3 - Compacting

Add the following:

Compaction of exposed site soil, backfill, fill, and base course materials shall be accomplished to the following density criteria:

<u>Material</u>	<u>Minimum Percent Compaction (ASTM D698)</u>
Subgrade Soil:	
Below structural elements	95
Below Pavement	95
Within three (3) feet of existing perimeter walls	85
Backfill:	
Below channel lining	95
Restoration of channel bank	95
Against structures	95

Compaction of granular soil below the channel lining should be accomplished at a moisture content between optimum minus 3 percent and optimum plus 3 percent.

Where existing Tatum Wash channel banks have been removed or re-graded for construction purposes, said banks shall be restored to original lines and grades. No separate payment will be made for the restoration of channel banks, but shall be considered incidental to related construction activities for which payment is provided.

On site undisturbed soils or compacted soils subsequently disturbed or removed by construction operations should be replaced by materials compacted as specified above.

Subsection 211.5 - Measurement

Replace this Subsection with the following:

No measurement will be made for fill construction. The estimated quantity for fill is 1,100 cubic yards.

Subsection 211.6 - Payment

Replace this Subsection with the following:

No payment will be made for fill construction, the cost thereof shall be included in the price bid for the Detention Basin Excavation to which such fill construction is considered incidental or appurtenant.

SECTION 215 - EARTHWORK FOR OPEN CHANNELS

Earthwork for open channels shall conform to Section 215 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 215.1 - Description

Replace this subsection with the following:

Open channels for the purpose of this section shall mean open channels and basins where there is exposed cuts. The work in this section consists of excavation, fill, grading, and disposal of excavated and removed material for the construction of the detention basin and associated inlet channel.

Subsection 215.3 - Excavation

Add the following:

The soil boring logs and geotechnical report (see Subsection 102.4) indicate that ripping may be necessary for the moderately to strongly cemented material below 10 feet. The Contractor is encouraged to review the soil boring logs included in Appendix A of these Special Provisions, and the geotechnical report as discussed in Subsection 102.4.

Subsection 215.7 - Measurement

Replace this subsection with the following:

Measurement for excavation material on site for the detention basin and the inlet channel will be made according to the quantity of material excavated from natural ground to the finished grades shown on the plans. No measurement will be made for fill construction, imported material, or disposal of excess material. The Engineer will verify the quantities of excavation by a method which in his opinion is best suited to obtain an accurate determination.

Subsection 215.8 - Payment

Replace this subsection with the following:

Payment for excavation of material for the detention basin and associated inlet channel will be made on the basis of the price bid per cubic yard of excavation.

ITEM 215-1 - DETENTION BASIN EXCAVATION

220 - RIPRAP CONSTRUCTION

Riprap construction shall conform to Section 220 of the MAG Uniform Standard Specifications except as modified herein:

Subsection 220.1 - Description

Replace this subsection with the following:

The construction of riprap shall consist of furnishing and placing stone adjacent to the inlet spillway structure walls and at the base of the inlet spillway structure as shown on the plans and specified in the special provisions. Sacked concrete riprap will not be allowed.

Subsection 220.4 - Plain Riprap

Replace this subsection with the following:

The construction of plain riprap shall consist of furnishing and placing the stones as shown in the plans and as specified in these special provisions.

Riprap Gradation Table ($D_{50} = 18''$)	
Stone Size (in)	Percent Gradation
1.5 d_{50}	100
1.2 d_{50}	85
1.0 d_{50}	50
0.4 d_{50}	15

Subsection 220.7- Measurement

Replace this subsection with the following:

Riprap shall be measured by the cubic yard of the rock placed to the depth and neat lines as shown on the plans. No measurement will be made for riprap placed beyond the neat line as shown on the plan unless directed by the Engineer.

Subsection 220.8 - Payment

Replace this subsection with the following:

Payment for plain riprap shall be made on the basis of the price bid per cubic yard in place; within the limits of dimensions shown on the plans for bid items 220-1. Payment shall include labor, preparation of ground surfaces, excavation, rip rap, replacement of damaged areas, samples provided for the Engineer's approval and all other miscellaneous items required for rip rap construction.

ITEM 220-1 - PLAIN RIPRAP

SECTION 225 - WATERING

Water for compacting and dust control shall conform to Section 225 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 225.1 - Description

Replace this subsection with the following:



The project site is located within a densely developed residential area. Therefore, pre-soaking prior to excavation, and continuous dust control efforts during construction will be required for this project. The Contractor will maintain adequate pre-soak conditions during excavation, and adequate dust control during loading and transport operations to minimize dust.

Subsection 225.2 - Water Supply

Replace this subsection with the following:

The Contractor is to use City of Phoenix water. The Contractor shall use only those hydrants designated by the City of Phoenix Water Services Department and in strict accordance with its requirements for hydrant use.

The Contractor shall contact the Water Services Department, Technical Support Group at 495-5601 to obtain a "Permit to Use Water from Fire Hydrant" and pay the required fees, which include both monthly services charges, plus the cost of the water per 100 cu. Ft units used.

Subsection 225.4 - Measurement

Replace this subsection with the following:

The Contractor must obtain a hydrant meter from the City of Phoenix to measurement the amount of water used. Measurement will be made based upon meter readings rounded to the nearest 100 cubic feet.

The Contractor shall furnish all connections, wrenches, valves and small tools that may be necessary to meet the requirements pertaining to the hydrant use.

Subsection 225.5 - Payment

Replace this subsection with the following:

Payment will be made on the basis of the price charged by the City of Phoenix per 100 cubic feet of water including taxes. Payment shall be for the cost of the water only; the cost of renting the meter, connecting and disconnecting the meter, applying the water including but not limited to the equipment, hauling, and labor, shall be considered incidental to the items for which watering is incidental.

ITEM 225-1 - WATERING

SECTION 301 - SUBGRADE PREPARATION

Subgrade preparation shall conform to Section 301 of the MAG uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 301.1 - Description

Replace this subsection with the following:

Subgrade preparation is for the detention basin maintenance access roads which are located along the east, west, and north sides of the detention basin.

Subsection 301.8 - Payment

Replace this subsection with the following:

No payment for subgrade preparation will be made as such; the cost thereof shall be included in the price of excavation.

SECTION 336 - PAVEMENT MATCHING AND SURFACING REPLACEMENT

Pavement matching and surfacing replacement shall conform to Section 336 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 336.2.2 - Pavement to be Removed

Add the following to this subsection.

All pavement to be removed shall first be sawcut.

Subsection 336.3 - Types and Locations of Pavement and Surfacing Replacement

Add the following to this subsection.

The replacement of asphaltic concrete pavement shall be 12" in thickness and shall match the grades of the existing pavement.

The materials shall conform to MAG Sections 702 and 710, and the following:

Asphaltic Concrete Type	C-3/4
Mineral Filler	Portland Cement (1-1/2% by weight)
Asphalt Cement	AC-20

Subsection 336.4 - Measurement

Replace this subsection with the following:

Measurement for payment will be by the square yard. In computing the pay quantities for replacements, the pay width will be measured to the outside of the trench not to exceed the maximum trench widths as listed as listed in Table 601-1 of the MAG Standard Specifications and along the longitudinal length of the pipe including through junction structures and/or manholes or as directed by the Engineer. Any pavement replacement in excess of this amount shall be considered and included in the bid item for such that the work is incidental or appurtenant.

Subsection 336.5 - Payment

Replace this subsection with the following:

Payment for pavement matching and surfacing replacement shall be made on the basis of the price bid per square yard, including all materials and subgrade preparation.

ITEM 336-1 - PAVEMENT REPLACEMENT

SECTION 340 - CONCRETE CURB, GUTTER, SIDEWALK, DRIVEWAY AND ALLEY ENTRANCE

Concrete curb, gutter, sidewalk, and driveways shall conform to Section 340 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 340.1 - Description

Add the following:

The work shall include the construction of concrete curb and gutter sections and sidewalk to replace and match existing curb, gutter, and sidewalk removed for the construction of the outlet pipe as identified in the plans.

The work also includes construction of concrete driveways with curb and gutter. Pavement removal and replacement necessary for construction of the driveways shall be considered incidental to the construction of the driveways (See Appendix 'B' for Driveway Detail P-1255-1).

Subsection 340.6 - Payment

Replace this subsection with the following:

Payment for concrete curb and gutter (MAG Det. 220 Type 'A') shall be made on the basis of the price bid per linear foot and shall be full compensation for all construction equipment, labor, materials, pavement removal and replacement if necessary, and all incidentals necessary to accomplish the work in conformance to the plans.

ITEM 340-1 - CONCRETE CURB AND GUTTER

Payment for concrete driveway entrance (COP Detail P-1255 and COP Detail P-1255-1, 9" thick) shall be made on the basis of the price bid per square foot and shall be full compensation for all construction equipment, labor, materials, pavement removal and replacement if necessary, and all incidentals necessary to accomplish the work in conformance to the plans.

ITEM 340-2 - CONCRETE DRIVEWAY ENTRANCE

Payment for concrete sidewalk (COP DET. P-1230) shall be made on the basis of the price bid per square foot and shall be full compensation for all construction equipment, labor, materials, and all incidentals necessary to accomplish the work in conformance to the plans. .

ITEM 340-4 - CONCRETE SIDEWALK

SECTION 350 - REMOVAL OF EXISTING IMPROVEMENTS

Removal of existing improvements shall conform to Section 350 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 350.1 - Description

Add the following:

The work includes the removal and disposal of an existing drainage inlet, concrete channel lining and other obstacles to construction, unless it is specifically called out on the plans to be removed and salvaged or protected in place. Holes, cavities and trenches resulting from the removal of structures shall be backfilled if necessary in accordance with Sections 206 and 211. The disposal of all waste material removed under this item shall be the responsibility of the Contractor. The disposal site shall be approved by the Engineer.

If a Maricopa County landfill is selected for the disposal of waste materials and/or debris, a Maricopa County Landfill Use Permit will be required. Application for permit can be made at the Maricopa County Landfill Office, located at 2801 West Durango Street, Phoenix, Arizona 85009 (telephone (602) 269-2661). Charges will be levied on a volume basis for each load delivered to the landfill in accordance with the current fee schedule.

In computing the pay quantities for removals, the pay width or length will be measured to the outside of the trench not to exceed the maximum trench widths as listed in Table 601-1 of the MAG Standard Specifications and along the longitudinal length of the pipe. The pay amount for the junction structure shall be as shown on the plans. Any removals in excess of this amount unless directed to be removed by the Engineer will not be measured and shall be included in the bid item for such that the removal is incidental or appurtenant.

Subsection 350.4 - Payment

No payment shall be made for the removal of trees.

No payment will be made for the removal and disposal of existing AC pavement as such; the cost thereof shall be considered incidental to the work that such removal is incidental or appurtenant.

Payment for removal and disposal of the existing drainage structure shall be made on the basis of the lump sum price bid. Payment shall be full compensation for furnishing all labor, materials, tools and equipment, sawcutting, removal, hauling, disposal and all other items necessary to accomplish the work and shall include the cost of installing pipe plugs in the two remaining pipes in accordance with the MAG Detail 427.

ITEM 350-1 - REMOVE DRAINAGE INLET STRUCTURE

Payment for removal and disposal of the shotcrete lining shall be made on the basis of the lump sum price bid. Payment shall be full compensation for furnishing all labor, materials, tools and equipment, sawcutting, removal, hauling, disposal and all other that is incidental or appurtenant.

ITEM 350-2 - REMOVE SHOTCRETE LINING

Payment for removal and disposal of existing concrete curb and gutter shall be made on the basis of the price bid per linear foot. Payment shall be full compensation for furnishing all labor, materials, tools and equipment, sawcutting, removal, hauling, disposal and all other items necessary to accomplish the work.

ITEM 350-3 - REMOVE CURB AND GUTTER

Payment for removal and disposal of existing concrete sidewalk, driveways, and aprons shall be made on the basis of the price bid per square foot. Payment shall be full compensation for furnishing all labor, materials, tools and equipment, sawcutting, removal, hauling, disposal and all other items necessary to accomplish the work.

ITEM 350-4 - REMOVE SIDEWALK

SECTION 401 - TRAFFIC CONTROL

Traffic control shall conform to Section 401 of the MAG Uniform Standard Specifications and COP Supplement to MAG except as modified herein.

Subsection 401.1 – Description

Replace this subsection with the following:

This work shall consist of traffic control devices and flagmen or pilot cars in accordance with Section 401 of the COP Supplement and the City of Phoenix Traffic Barricade Manual, latest revision.

- a. Traffic Control Devices
All traffic and/or traffic control devices on this project shall be provided, maintained and/or controlled as specified in the City of Phoenix Traffic Barricade Manual, latest revision.
- b. Street Closure Permits
Permission to restrict city streets, sidewalks and alleys (street closure permits) shall be requested as specified in Section III of the City of Phoenix Traffic Barricade Manual.
- c. Traffic Manual
Unless otherwise provided for in the following "General Traffic Regulations," all traffic on this project shall be regulated as specified in Section IV of the City of Phoenix Traffic Barricade Manual.
- d. Prior Approval
No deviation to the "General Traffic Regulation" will be allowed or implemented unless submitted to the Engineer for review and approval two weeks prior to the proposed work.

Subsection 401.5 – General Traffic Regulations

- a. Local Access Requirements
The Contractor shall maintain local access to all side streets, access roads, driveways, alleys, and parking lots at all times and shall notify residents 72 hours in advance of any restrictions which will affect their access. The Contractor shall restore the access as soon as possible. If the primary access cannot be restored in a timely manner, the Contractor shall provide an alternative, which shall be predetermined with the residents prior to imposing any restrictions. Any local street restrictions imposed shall be such that local area traffic circulation is maintained unless specified to be closed herein or as shown on the detour plans.
- b. Flagging of Traffic
No flagging of traffic in the eastbound direction will be permitted during the peak traffic hours of 4:00 p.m. to 7:00 p.m. weekdays. No flagging of traffic in the westbound direction will be permitted during the peak traffic hours of 6:00 a.m. to 9:00 a.m. and 4:00 p.m. to 7:00 p.m. weekdays. Intermittent flagging of traffic in both directions will be allowed at all other times, and including between 7:00 p.m. Friday evenings and 6:00 a.m. Monday morning to facilitate construction and access for heavy construction equipment.
- c. Traffic Control Plan
The Contractor shall submit a Traffic Control Plan (TCP) for approval, showing placement of all traffic control devices, including all conflicting signs to be covered/removed or relocated, or other features that may conflict with the placement of temporary signage. This plan shall be professionally drawn on a 24" x 36" reproducible medium, and shall be submitted to the Engineer at the Pre-Construction Conference meeting.
- d. Business Access Requirements
Access shall be maintained to adjacent businesses at all times during their hours of operation. Access may be maintained by such measures as constructing driveways in half sections, or by providing bridging over new concrete. Properties having more than one point of access shall not have more than one access restricted for more than fourteen (14) calendar days at any given time. Access to adjacent driveways shall be provided during all non-working hours. Any business restrictions shall be coordinated with the affected business in writing at least seven (7) days prior to imposing restrictions.
- e. Pedestrian Access Requirements
The Contractor shall ensure that all sidewalks on this project remain open and safely usable at all times. Such measures as backfilling or ramping to existing sidewalks, or providing alternate sidewalk areas adjacent to existing sidewalks may be used. In high pedestrian use areas, the

Engineer may request temporary hard-surface walkways, such as plywood sheets to be installed at no additional cost to the District.

f. Bus Stops

The Contractor shall maintain all existing bus stop locations on this project in a safe manner, or provide alternate bus stop locations as required by the Engineer.

g. Sanitation Pickup

The Contractor shall provide sanitation pickup for affected residents by relocating trash containers, or by providing alternative measures acceptable to the Sanitation Division of the City of Phoenix Public Works Department.

h. Special Notification Signs

The Contractor shall provide and install two variable message signs for advanced public notification in lieu of post mounted signs for restrictions on Shea Blvd. These signs shall display the information shown below in the following order:

- * Location of Work
- * Type of Restriction
- * Time of Restriction
- * Advisory Note

Signs should be placed to be seen from a distance of 300 feet, or as directed by the Engineer. These signs shall be installed two weeks prior to the start of construction for the restriction.

i. Special Sign Requirements

The Contractor shall provide, erect, and maintain informational and directional access signs that may be required by the Engineer. The cost shall be included in the bid item for Traffic Control Devices.

j. Traffic Control and Safety

At the time of the Pre-Construction Conference, the Contractor shall designate an employee, other than the Project Superintendent, who is well qualified and experienced in construction traffic and safety, to be available on the project site during all periods of construction to coordinate and maintain safe barricading whenever construction restricts traffic.

k. Coordination with COP Construction Traffic Control

The Contractor shall contact Tony Arviso at 262-6565 or John Perez at 495-6934 at Construction Traffic Control, City of Phoenix.

Subsection 401.5.1 – Special Traffic Regulations

Replace this subsection with the following:

- a. Shea Blvd is considered a major street and the following lane closure restrictions will apply:
- b. Saw cutting of existing pavement and/or replacement of permanent pavement shall be accomplished one lane at a time from 9:00 am to 4:00 pm on weekdays, and during daytime working hours on weekends, in order to minimize and mitigate night time construction noise, and impacts to peak travel times on Shea Blvd.
- c. For construction of the junction structure in Shea Boulevard the Contractor shall maintain two lanes of traffic in each direction, allowing one lane closure in the eastbound direction and two lane closures in the westbound direction, by utilizing the north side frontage road as an additional westbound lane. The Contractor must provide a detour plan sealed by a Registered Engineer to the City of Phoenix for approval prior to the implementation of any such lane modifications, usages, and restrictions.

- d. For construction of the outfall pipe in Shea Blvd. from the basin to the junction structure, the Contractor shall maintain two eastbound lanes, allowing one lane closure in the eastbound direction.
- e. For construction of the junction structure and installation of the outfall pipe weekend work will be allowed, including night time hours, between 7:00 pm on Friday and 6:00 am on Monday, on non-holiday weekends after September 9. During weekend work two lanes (one lane in each direction) must be maintained at all times. As of 6:00 am on Monday, traffic restrictions and construction requirements as stated in items "c" and "d" above will apply. The Contractor must provide a traffic control plan to the City of Phoenix for approval prior to the implementation of any such lane modifications, usages, and restrictions.
- f. For night time work on weekends the Contractor shall minimize noise disturbance to the surrounding residential areas by disengaging "back-up beepers" and utilizing back-up strobe lights with spotters, and by increasing the muffler capacities of all equipment.
- g. Prior to excavation, the Contractor shall:
 - 1. Develop a haul route plan and obtain a no fee permit from COP Development Services Department
 - 2. Obtain COP Street Transportation Department approval of haul route, truck volumes and operating hours.
 - 3. Obtain COP Development Services Department grading permit, including Floodplain Section if applicable, for the proposed spoil location
 - 4. Street Transportation Department permit does not release Contractor from MAG Subsection 108.5 requirements.
- h. For excavation and haul activities only, the right eastbound curb lane can be restricted from 7:00 am to 4:00 pm on weekdays and daytime working hours on weekends. During all other times, all eastbound lanes shall remain unrestricted. Ingress and egress access for the business immediately east of the project area must be addressed as part of any TCP.
- i. Construction activities within Shea Blvd. will be restricted during the holiday season of November 15 through January 1. Construction activities that interfere with traffic flow on high volume streets such as Shea Blvd. must be carefully evaluated and imposed only when absolutely necessary.

Subsection 401.7 - Payment

Replace this subsection with the following:

Payment for traffic control, including all mobilization, signage, materials, and maintenance shall be made on the basis of the lump sum price bid.

ITEM 401 -1 - TRAFFIC CONTROL

Payment for off-duty City of Phoenix uniformed officers as mandated by the City of Phoenix will be on an as-used basis as determined by the Engineer. The Contractor shall submit documentation as required by the Engineer to support payment for this item. Payment for off-duty uniformed officers shall be made on the basis of the contract unit price per hour.

ITEM 401-2 - OFF-DUTY UNIFORMED OFFICER

SECTION 440 - SPRINKLER IRRIGATION SYSTEM INSTALLATION

Sprinkler irrigation system installation shall conform to Section 440 of the Mag Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 440.1 - General:

Replace this subsection with the following:



The existing landscape irrigation system located along the sidewalk will be relocated and/or adjusted as necessary by the Contractor to keep the irrigation system operational at all times during construction. Such relocation and/or adjustment may be necessary during the removal of existing features and/or installation of new construction.

Subsection 440.3 - Pipe Installation:

Add the following:

The work under this section shall include and apply to the existing relocation/modification of the existing irrigation line located in the vicinity of the East and West driveway entrances. The relocation/modifications shall consist of making any necessary changes to keep the integrity of the system intact after removing any necessary landscaping within the road rights-of-way and construction of the driveways.

Subsection 440.8 - Measurement and Payment

No measurement or payment for irrigation shall be made as such; the cost thereof shall be considered incidental to the cost of those construction activities requiring such removal or adjustment.

SECTION 505 - CONCRETE STRUCTURES

Structural concrete shall conform to Section 505 of the MAG Uniform Standard Specifications except as modified herein.

Subsection 505.1 - Description

Add the following:

The work under this section shall consist of furnishing all labor, materials and equipment for the construction of all cast-in-place and other concrete structures including the concrete inlet spillway structure, the junction structure, and the basin outlet structure as located and indicated on the plans.

Concrete shall conform to the requirements of Section 725 of the MAG Uniform Standard Specifications, and mix designs shall additionally meet the requirements of Chapter 5, Section 5.3 of ACI STANDARD 318-89. The Contractor shall submit mix designs and certifications of conformance with the above requirements for the written approval of the Engineer.

Class "A" Concrete, $f'c = 3,000$ psi, shall be used for all concrete structures and concrete channel lining.

The use of Class F fly ash will be permitted in all concrete mixes, subject to approval of mix design by Engineer.

Transit Concrete mixes used on the project must carry current certification from ADOT or Arizona Rock Products Association.

The reinforcing steel shall conform to Section 727, Grade 60, of the MAG Uniform Standard Specifications.

The 3" PVC weep holes shall be installed as shown on the plans.

Shop Drawings shall be submitted for the following:

1. Product Data: Admixtures and patching materials.
2. Placement Drawings:
 - a. Concrete, identifying location of each type of construction joint.
 - b. Reinforcing steel.
3. Plastic Type Water Stops: Details of splices to be used and method of securing water stop in the forms and supporting water stop so as to maintain proper orientation and location during concrete placement.

Do not backfill against walls until concrete has obtained 28-day compressive strength. Place backfill simultaneously on both sides of wall, where required, to prevent differential pressures.

Subsection 505.6 - Placing Concrete

Add the following:

Place concrete in accordance with ACI 301-89. Prior to placing concrete, remove loose soil and water from excavation and subgrade and debris and foreign material from forms. Obtain Engineer's approval of subgrade before placing reinforcing steel. Check reinforcing steel for proper placement and correct discrepancies. Before depositing new concrete on old concrete, clean surface using sandblast or bushhammer or other mechanical means to obtain a 1/4-inch rough profile. Maximum vertical drop to final placement shall be 6 feet, when not guided with chutes or other devices to prevent segregation caused by impact with reinforcing. Do not use aluminum pipe or aluminum conveying devices.

Steps performed in preparation for placing concrete shall meet requirements and recommendations of ACI 304R-89 and ACI 301-89, except as modified herein. Ends of chutes, piping, hopper gates, and other points of concrete discharge throughout the conveying, hoisting, pumping, and placing system shall be designed and arranged for concrete to pass without becoming segregated. Do not use chutes longer than 50 feet. The minimum slopes of chutes shall be angled to allow concrete to readily flow without segregation. Conveyor belts shall be approved by Engineer; wiped clean with device which does not allow mortar to adhere to belt; and conveyor belts and chutes covered.

Provide standby pump, conveyor system, crane and concrete bucket, or other system onsite during placing, for adequate redundancy to ensure completion of concrete placement without cold joints in case of a primary placing equipment breakdown. Minimum pump hose (conduit) diameter shall be 4 inches. Replace pumping equipment and hoses (conduits) that are not functioning properly.

Provide intermediate construction joints at maximum spacing of 30 feet. Should placement sequence result in cold joint, install water stop in joint.

Limit size of each placement to allow for strength gain and volume change caused by shrinkage. Minimum time between adjacent placements for construction of the spillway floor slab shall be seven (7) days.

Consolidate concrete with internal vibrators with minimum frequency of 8,000 cycles per minute and amplitude required to consolidate concrete in section being placed. Provide at least one standby vibrator in operable condition at placement site prior to placing concrete. Consolidation equipment and methods shall conform with the requirements of ACI 309R-87. Provide sufficient windows in forms or limit form height to allow for concrete placement through windows and for visual observation of concrete. Vibration consolidation shall not exceed a distance of 5 feet from point of placement. Vibrate concrete in vicinity of joints to obtain impervious concrete there.

When vibrating concrete, apply approved vibrator at points spaced not farther apart than vibrator's effective radius. Apply close enough to forms to vibrate surface effectively but not damage form surfaces. Vibrate until concrete becomes uniformly plastic. Vibrator must penetrate fresh placed concrete and into previous layer of fresh concrete below.

Subsection 505.6.1 - Joints

Add the following:

To new concrete wall horizontal construction joints, thoroughly clean and saturate joint with water. Cover horizontal wall surfaces with minimum 2 inches of grout, as specified in Section 732, and immediately place concrete. Limit concrete lift placed immediately on top of grout to 12 inches thick. Thoroughly vibrate to mix and consolidate grout and concrete together.

To old concrete (greater than 60 days old), mechanically roughen existing concrete surfaces to a clean, rough surface using a "Blastrac" by Wheelabrator-Frye, Inc.; or "Porta-Shotblast" by Nelco Manufacturing Corp, to remove existing concrete surface, and provide a minimum roughness profile of 1/4-inch. Saturate surface with water for 24 hours, cover with 2 inches of grout, and place grout as specified for new concrete.

Construction joints shall be constructed as straight joints and made either vertical or horizontal. Concrete placement shall commence after the joint preparation is complete.

For construction joints, prior to placement of abutting concrete, clean contact surface by removing laitance and spillage from reinforcing steel and dowels. Then roughen surface to a minimum of 1/4-inch amplitude by either sandblasting after the concrete has fully cured, water blasting after the concrete has partially cured, or if the concrete is green, cutting the fresh concrete with high pressure water and hand tools. Perform cleaning so as not to damage water

stop, if one is present.

Join water stops at intersections to provide continuous seal. Center water stop on joint. Secure water stop in correct position to avoid displacement during concrete placement. Repair or replace damaged water stop. Place concrete and vibrate to obtain impervious concrete in the vicinity of all joints. For joints in slabs, make sure that the space beneath plastic water stop is completely filled with concrete. Also, during concrete placement, make a visual inspection of the entire water stop area. Limit concrete placement to elevation of water stop in first pass, vibrate the concrete under the water stop, lift the water stop to confirm full consolidation without voids, then place remaining concrete to full height of slab. Apply procedure to full length of plastic water stops.

Plastic water stops shall be installed in accordance with manufacturer's written instructions. Splice in accordance with the water stop manufacturer's written instructions using a thermostatically controlled heating iron. Butt splice unless specifically detailed otherwise. Allow at least 10 minutes before the new splice is pulled or strained in any way. Finished splices shall provide a cross section that is dense and free of porosity with tensile strength of not less than 80 percent of the unspliced materials. Wire looped plastic water stop may be substituted for plastic water stop.


Subsection 505.8 - Curing

Add the following:

Use one of the following methods as approved by Engineer.

Walls shall have only water curing procedures used. Method 1: Leave concrete forms in place and keep entire surfaces of forms and concrete wet for 10 days. Method 2: Continuously sprinkle with water 100 percent of exposed surfaces for 10 days starting immediately after removal of forms.

Slabs shall use one of the following methods: Method 1: Protect surface by water ponding for 10 days; Method 2: Cover with burlap or cotton mats and keep continuously wet for 10 days; Method 3: Cover with 1-inch layer of wet sand, earth, or sawdust, and keep continuously wet for 10 days; or Method 4: Continuously sprinkle exposed surface for 10 days. Other agreed-upon methods that will keep moisture present and uniform at all times on surface of slabs. Do not use curing compounds.



Subsection 505.9 - Finishing Concrete

Add the following:

A heavy rake finish shall be applied to the floor of the inlet spillway structure prior to the sloping surface. The sloping surface of the spillway shall have a rough broom finish applied to the floor.

All exposed concrete structures including the concrete channel lining, inlet spillway structure, and the outlet structure shall be colored using a "light brown" admixture. The color shall conform to Davis Color "Flag Stone Brown #64" as manufactured by Davis Colors, or an approved equal, with respect to hue, value, and chroma. A test panel shall be made and the concrete color shall be approved by the Engineer prior to use. The color shall be added at the rate of 2 pounds per 94-pound sack of cement. The cost of the coloring is incidental to the cost of the concrete.

A clear protective water based coating shall be applied to all exposed concrete structure surface areas. The coating shall be Graffiti Protector #J-44, produced by Dayton Superior, or approved equal. The coating shall be clear and contain no coloring. The cost of the coating is incidental to the cost of the concrete.

A form liner shall be used for the finish on the north, east, and west vertical faces of the outlet structure. The form liner shall be VA D.O.T. Fractured Rib design, No. 367, uni-cast and/or multi-cast sheets as manufactured by Greenstreak, or approved equal. Form liners shall be prepared, placed and stripped per the manufacturer's requirements, recommendations and specifications. The form liner shall not infringe on or reduce the required thickness of the retaining wall as detailed on the plans. The cost of the form liner is incidental to the cost of the outlet structure.

Prior to starting patching work, obtain quantities of color-matched patching material and manufacturer's detailed instructions for use to provide a structural patch with finish to match adjacent surface. Develop patching techniques with epoxy manufacturer on mockup panel. Dress surface of patches that will remain exposed to view to match color and texture of adjacent surfaces. Patching of concrete shall provide a structurally sound surface finish, uniform in appearance or upgrade finish by other means until acceptable to Engineer.

For tops of walls, screed surfaces to true level planes. After initial water has been absorbed, float with wood float and trowel with steel trowel to smooth finish free from trowel marks.

Spray evaporation retardant onto surface of fresh flatwork concrete immediately after screeding to react with surface moisture. Reapply as needed to ensure a continuous moist surface until final finishing is completed.

Subsection 505.9.6 - Finishing and Patching Surfaces

Add the following new section:

When patching *defective* areas, remove *defective* concrete to a depth of sound concrete. Small shallow holes caused by air entrapment at surface of forms shall not be considered *defective* unless amount is so great as to be considered not the standard of the industry. Obtain Engineer's approval of chipping work.

Cut out honeycombed and *defective* areas. Cut edges perpendicular to surface at least 1 inch deep. Do not feather edges. Soak area with water for 24 hours. Patch with nonshrink grout as specified in Section 732. Finish surfaces to match adjacent concrete. Keep patches damp for minimum 7 days or spray with curing compound to minimize shrinking.

To patch form tie holes, fill with Category I grout as specified in Section 732. Use only enough water to dry pack. Compact grout using steel hammer and steel tool to drive grout to high density. Cure grout with water. Make sure color of patch after curing matches color of adjacent concrete.

Subsection 505.10 - Payment

Payment for concrete structures shall be made on the basis of the price bid cubic yard of concrete. Payment shall be full compensation for all labor, materials, reinforcing steel, access barriers, and grates, equipment, excavation and backfill, color admixture, protective coating, and all other items necessary and incidental to construct the structures complete in place according to the plans and these Special Provisions excluding the flapgates.

ITEM 505-1 - SPECIAL OUTLET STRUCTURE

ITEM 505-2 - SPECIAL INLET SPILLWAY

Payment for the Special Junction Structure shall be made on the lump sum price bid. Payment shall be full compensation for all labor, materials, reinforcing steel, equipment, excavation and backfill, color admixture, protective coating, and all other items necessary and incidental to construct the structures complete in place according to the plans and these Special Provisions.

ITEM 505-3 - SPECIAL JUNCTION STRUCTURE

SECTION 515 - STEEL STRUCTURES

Steel Structures shall conform to Section 515 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 515.1 - Description

The work under this section shall consist of supplying and installing Waterman Model F-10 or approved equivalent flapgates and the inlet grates and access barriers and associated embedments for the outlet structure according to the plans and these Special Provisions.

All material for the inlet grate and access barrier shall be A36 steel.

The inlet grates, access barriers and associated embedments shall be galvanized in accordance with MAG Section 771.

Subsection 515.7 - Payment

No payment will be made for access barriers, or inlet grates and associated embedment angles as such, the cost thereof shall be included in cost of the Special Junction Structure. Payment for flapgates shall be made on the basis of the lump sum price bid per each. Payment shall be full compensation for all labor, materials, equipment, and all other items necessary to complete the work in place according to the plans and these Special Provisions.

ITEM 515-1 - 24" FLAP GATE

SECTION 520 - STEEL HANDRAILS

Steel handrails shall conform to Section 520 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 520.1 - Description

Add the following:

The work under this section shall include providing and erecting steel handrails and pipe gates as shown in the plans.

All steel handrails and pipe gates shall be painted in accordance with MAG Section 790. The paint color shall be a light brown in color as approved by the Engineer.

Subsection 520.5 - Payment

Payment for handrails shall be made on the basis of the price bid per linear foot. Payment shall be full compensation for all labor, materials, equipment, and painting, and all other items necessary to complete the work in place according to the plans and these Special Provisions.

ITEM 520-1 - STEEL HANDRAILS

Payment for pipe gates shall be made on the basis of the lump sum price bid per each gate. Payment shall be full compensation for all labor, materials, equipment, and painting or galvanizing and all other items necessary to complete the work in place according to the plans and these Special Provisions.

ITEM 520-2 - STEEL PIPE GATE

SECTION 525 - PNEUMATICALLY PLACED CONCRETE

Subsection 525.1 - Description

Add the following:

The work under this section shall include the placement of shotcrete lining on the side slopes of the existing Tatum Wash upstream of the inlet spillway structure as shown in the plans.

Subsection 525.12 - Payment



Replace this subsection with the following:

Payment for shotcrete lining shall be measured on the basis of the price bid per square yard of exposed surface plus the area of any toedown. Payment shall be full compensation for all labor, materials, reinforcing steel, equipment, excavation and backfill, color admixture, coating, and all other items necessary and incidental to construct the lining complete in place according to the plans and these Special Provisions.

ITEM 525 -1 SHOTCRETE CHANNEL LINING

SECTION 601 - TRENCH EXCAVATION, BACKFILLING AND COMPACTION

Trench excavation, backfilling and compaction shall conform to Section 601 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 601.4.2 - Bedding:

Add the following:

This work shall include the placement of cement-treated slurry bedding as specified on the plans and in these Special Provisions.

Cement-treated slurry bedding material shall conform to the gradation specified for bedding material to the requirements set forth in MAG Section 728. Cement-treated slurry shall have a slump of 8 to 11 inches and have a minimum of 25 psi compressive strength and a maximum of 1000 psi based on a 28 day test.

Cement-treated slurry bedding material shall be placed in a uniform manner that will prevent voids in, or segregation of, the bedding material, and will not float or shift the pipe. Cement-treated slurry bedding material shall be placed from bottom of pipe to pipe spring line. No backfilling above the cement-treated slurry shall be commenced until 24 hours after the cement-treated slurry has been placed.

Subsection 601.4.3 - Backfill:

Add the following:

The Contractor may opt to use cement treated slurry aggregate base course in place of native backfill. The backfill begins from the springline to within one (1) foot from the top of the trench.

Cement-treated slurry backfill material if used shall conform to the gradation specified for bedding material in the COP Supplement Subsection 601.4.2 and to the requirements set forth in MAG Section 728. Cement-treated slurry shall have a slump of 8 to 11 inches and have a minimum of 25 psi compressive strength and a maximum of 1000 psi based on a 28 day test.

Cement-treated slurry pipe backfill shall be placed in a uniform manner that will prevent voids in, or segregation of, the backfill to a maximum elevation one foot from the top of trench and as required per plans. No backfilling above the cement-treated slurry pipe backfill above the cement-treated slurry pipe backfill shall be commenced until 24 hours after the cement-treated slurry has been placed.

Subsection 601.6 - Payment:

No payment will be included in the proposal, nor direct payment made for trench excavation, foundation, bedding, backfilling, compaction, or placement of temporary pavement. The cost of these features of the work shall be included in the unit price bid per linear foot for furnishing and laying pipe.

SECTION 615 - SEWER LINE CONSTRUCTION

Sewer line construction shall conform to Section 615 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 615.1 - Description

Add the following:

The work in this section shall include replacing the existing 15" sewer with ductile iron pipe at its crossing below the proposed 42" outlet structure pipe.

All ductile iron pipe shall be in accordance with AWWA C-150

A. Materials and Lining for Ductile Iron Sewer

All ductile iron pipe for conveying sewage shall be in accordance with AWWA C-150:

Ductile iron pipe with a minimum wall thickness of Class 52 may be substituted in lieu of the above.

The lining shall cover, at a minimum, the inner surfaces of the pipe and the fitting from the plain end or beveled spigot end to the rear of the gasket socket. If flanged fittings and pipe are included in the project, the lining must not be used on the face of the flange, however full face gaskets must be used to protect the ends of the pipe. At the ends of the pipe and fittings, the lining thickness shall taper for a distance of 4 inches to a minimum thickness of 10 mils.

All ductile iron sewer pipe shall have a protective lining with a nominal thickness of 40 mils and a minimum thickness of 35 mils of Protecto 401 (ceramic epoxy), Polythane (polyurethane), SewerCoat (calcium aluminate), or approved equal throughout the barrel area of the pipe. However, the lining in the bell area shall transition to a minimum thickness of 10 mils at the edge of the gasket socket. The 10 mil lining shall extend into the gasket socket area to a point where the gasket would overlap the lining when it is compressed due to pipe assembly during construction. The 10 mil lining shall also continue from inside the barrel area, around the spigot end of the pipe and along the outside of the pipe to a point where the center of the gasket of the next pipe section would contact the edge of the lining on the spigot end of the previous pipe section. The thickness of the linings shall be determined by using a dry film thickness magnetic gauge at four quadrants.

Each section of pipe and each fitting shall be tested and shall have an absence of holidays when tested by a suitable holiday detector. In all cases, the barrel area of the pipe shall be tested using a voltage of 7,500 volts and a dry conductive probe.

Holiday testing shall conform to ASTM G 62-87 and NACE Standards RP0274-74 and RP0188-90 (latest revision).

The pipe manufacturer shall be solely responsible for the quality of the lining and shall supply a certification as to compliance to the specification. The certification shall state specifically the following items:

- 1) All ductile sewer pipe and fittings have a protective lining of 40 mils (35 mils min) in the barrel area, 10 mils in the bell area and 10 mils minimum on the exterior of the spigot end.
- 2) Each section of pipe and each fitting have been tested for holidays utilizing a test voltage of 7,500 volts with a dry conductive probe in the barrel area and a test voltage of 67.5 volts with a wet sponge in both the bell area and the exterior of the spigot end, and no holidays were found.
- 3) The lining material used meets the current specifications and that the material was applied as required by the specification.

If the contractor makes a field cut of the lined ductile pipe, the Contractor shall comply with the recommendations of the pipe manufacturer in applying a field coating to the end of the pipe ends. In all cases, as a minimum, a 10 mils coating shall be applied to the pipe end and shall overlap the lining by four inches and extend around the pipe end and along the outside of the pipe a minimum of ten inches. The coating shall be allowed to dry before assembly. In addition, the overlapped surface of the lining shall be roughed up to produce a 3 to 5 mil profile over the entire surface. The end result of this process is to secure proper adhesion of the field coating.

B. Repair

Repair of the damaged sections of the lining shall be in accordance with the lining manufacturer's recommendation or as specified above so that the repair area is equal to the undamaged lined area in all respects. All damaged lined areas and holidays shall be repaired immediately after discovery.

Holiday testing may be required by the Engineer before pipe assembly when deemed appropriate. The testing and repair requirements shall follow the procedures called for in this specification and all costs for such repairs will be the responsibility of the Contractor.

There will be no other provisions for repair of the lining of DIP.

C. Protective Collar

In order to protect the exterior spigot end against abrasion and damage during shipping and handling, the manufacturer shall install temporary collars on the exterior of each spigot end of each pipe section. The manufacturer shall secure the collars to the pipe to prevent accidental removal during shipping and normal handling by the Contractor. The collars are not to be removed from the pipe until right before the pipe section is to be installed or field cut.

D. Sewer Inspection

The COP must TV inspect and approve the completed DIP sewer line installation after backfilling of the pipe has been done. The Contractor shall contact Gerry Arakaki at the WSD at 261-8229 a minimum of 48 hours in advance of the need to do the TV inspection.

Subsection 615.13 - Measurement and Payment

Replace this subsection with the following:

Measurement will be made horizontally along the length of the pipe rounded to the nearest foot including all fittings.

Payment for sewer pipe construction shall be made at the unit price bid per linear foot, and shall be full compensation for furnishing and installing the pipe, lining, and fittings complete in place, as specified, including excavation, removals if necessary, backfilling, compaction, sheeting and bracing, testing, and all incidental work not specifically covered in other pay items.

ITEM 615-1 - 15" DIP, CL 52

SECTION 618 - STORM DRAIN CONSTRUCTION

Storm drain construction shall conform to Section 618 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 618.1 - Description

Add the following:

The work applies to the storm drain pipe connecting the outlet structure with the junction structure in Shea Boulevard.

Subsection 618.2 - Materials

Add the following:

Concrete pipe, joints, gaskets, and testing shall be according to MAG Section 735 and as specified below.

Location	Storm drain construction from the basin outlet structure to the storm drain junction structure.
Type	Rubber Gasketed Reinforced Concrete Pipe (RGRCP), ASTM C 76
Class	IV
Diameter	42 inch
Joints	Rubber Gasket Bell and Spigot

Subsection 618.5 - Measurement

Replace this subsection with the following:

Measurement will be made horizontally along the axis of the pipe rounded to the nearest foot including all fittings.

Measurement shall extend from the inside face of the outlet to the inside face of the junction structure.

Subsection 618.6 - Payment

Payment for storm drain construction shall be made at the unit price bid per linear foot, and shall be full compensation for furnishing and installing the pipe and fittings complete in place, as specified, including excavation, removal of AC pavement, backfilling, compaction, sheeting and bracing, testing, and all incidental work not specifically covered in other pay items.

ITEM 618-1 - 42" RGRCP

SECTION 650 - INSTRUMENTATION CONDUIT

Add this section to the MAG Uniform Standard Specifications.

Subsection 650.1 - Description

The work in this section shall include installing galvanized and pvc conduit to facilitate the future installation of weather monitoring equipment.

Subsection 650.2 - Conduit

Galvanized and Schedule 80 PVC in 2-inch diameter as required. Pipe shall conform to ASTM D 1785. Use Schedule 80 fittings conforming to ASTM D 2467 withy primer and adhesive solvent connections conforming to ASTM D 2564. Install conduit as shown on plans. Provide and install 200-lb minimum test pull string in conduit.

Subsection 650.2 - Measurement

Measurement will be made horizontally along the length of the pipe rounded to the nearest foot including all fittings.

Subsection 650.2 - Payment

Payment for instrumentation conduit installation shall be made at the unit price bid per linear foot, and shall be full compensation for furnishing and installing the pipe and fittings, concrete collar, excavation, compaction, and all incidental work not specifically covered in other pay items to complete this item in-place as specified.

ITEM 650-1 - 2" Dia Instrumentation Conduit

SECTION 725 - PORTLAND CEMENT CONCRETE

Portland cement concrete shall conform to Section 725 of the MAG Uniform Standard Specifications and COP Supplement except as modified herein.

Subsection 725.2 - Portland Cement

Add the following:

Cement shall be Portland Cement, conforming to the requirements of ASTM C-150, Type II, unless noted otherwise on the plans or in the specifications.

Subsection 725.6 - Admixtures

Add the following:

When an air-entraining agent is authorized, the amount used will be limited to the extent that the amount of air by volume shall not be less than 4 percent nor more than 6 percent. Air-entraining agents complying with AASHTO M-154 or ASTM C-260 will be permitted as long as strength requirements are met. Any admixture shall be measured accurately by mechanical means into each batch by equipment and in a method approved by the Engineer.

19

BIDDING SCHEDULE

Engineer's Estimate

PROJECT: Tatum Wash Detention Basin No. 1

CONTRACT: FCD 97-22

ITEM NO.	DESCRIPTION	UNIT	APPROX QTY.	UNIT COST NUMBERS	EXTENDED AMOUNT
105 - 1	Partnering	LS	1	\$5,000.00	\$5,000.00
107 - 1	NPDES/ SWPPP Permits	LS	1	\$5,000.00	\$5,000.00
107 - 2	Public Information and Notification Allowance	LS	1	\$25,000.00	\$25,000.00
107 - 3	Project Signs Allowance	LS	1	\$2,000.00	\$2,000.00
201 - 1	Clearing and Grubbing	LS	1	\$5,000.00	\$5,000.00
202 - 1	Mobilization	LS	1	\$15,000.00	\$15,000.00
215 - 1	Detention Basin Excavation	CY	77,534	\$5.50	\$426,437.00
220 - 1	Plain Riprap	CY	289	\$45.00	\$13,005.00
225 - 1	Watering	100/CF	2,675	\$1.19	\$3,183.25
336 - 1	Pavement Replacement	SY	98	\$35.00	\$3,430.00
340 - 1	Concrete Curb & Gutter	LF	107	\$7.50	\$802.50
340 - 2	Concrete Driveway Entrance	SF	464	\$5.00	\$2,320.00
340 - 3	Concrete Sidewalk	SF	44	\$3.00	\$132.00
350 - 1	Remove Drainage Inlet Structure	LS	1	\$1,500.00	\$1,500.00
350 - 2	Remove Shotcrete Lining	LS	1	\$3,000.00	\$3,000.00
350 - 3	Remove Curb & Gutter	LF	107	\$1.00	\$107.00
350 - 4	Remove Sidewalk	SF	205	\$1.00	\$205.00
401 - 1	Traffic Control	LS	1	\$10,000.00	\$10,000.00
401 - 2	Off Duty Uniformed Officer	HR	400	\$24.00	\$9,600.00
505 - 1	Special Outlet Structure	CY	14	\$400.00	\$5,600.00
505 - 2	Special Inlet Spillway	CY	630	\$400.00	\$252,000.00
505 - 3	Special Junction Structure	LS	1	\$15,000.00	\$15,000.00
515 - 1	24" Flapgate	EA	2	\$1,000.00	\$2,000.00
520 - 1	Steel Handrails	LF	644	\$25.00	\$16,100.00
520 - 2	Steel Pipe Gate	EA	3	\$1,200.00	\$3,600.00
525 - 1	Shotcrete Channel Lining	SY	107	\$28.00	\$2,996.00
615 - 1	15" DIP, CL 52	LF	16	\$120.00	\$1,920.00
618 - 1	42" RGRCP	LF	108	\$122.00	\$13,176.00
650 - 1	2" Dia Instrumentation Conduit	LF	63	\$6.00	\$378.00
					\$843,491.75



FLOOD CONTROL DISTRICT OF MARICOPA COUNTY

PLANS FOR THE CONSTRUCTION OF:
TATUM WASH DETENTION BASIN NO. 1
FCD PROJECT NO. 97-22

Shea 90^K Veh/day



EB ingress egress only

EB egress all times except pm peak


ONSITE VISIT MANDATORY

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET, VICINITY MAP & INDEX OF SHEETS
2	SITE & DEMOLITION PLAN
3-4	GRADING PLAN
5	TYPICAL SECTIONS
6	SPILLWAY DETAILS
7	FENCE DETAILS



PROJECT LOCATION




VICINITY MAP

Not to Scale

City of Phx

FLOOD CONTROL DISTRICT OF MARICOPA COUNTY	
ISSUED FOR PUBLIC BIDDING BY:	
CHIEF ENGINEER AND GENERAL MANAGER	
BOARD OF DIRECTORS OF THE FLOOD CONTROL DISTRICT	
DON STAPLEY - CHAIRMAN	
DISTRICT 1	FULTON BROCK
DISTRICT 2	DON STAPLEY
DISTRICT 3	BETSEY BAYLESS
DISTRICT 4	JAN BREWER
DISTRICT 5	MARY ROSE WILCOX



REMOVE

- 1 REMOVE CONCRETE INLET STRUCTURE, 1 EA.
- 2 REMOVE SHOTCRETE CHANNEL LINING, 1 L.S. (SEE SHEET 4 FOR LIMITS)

CONSTRUCT

3			
2			
1			
NO.	REVISION	BY	DATE

FLOOD CONTROL DISTRICT
OF MARICOPA COUNTY
ENGINEERING DIVISION

TATUM WASH DETENTION BASIN


	DESIGNED	MAL	DATE	06/13/97
	DRAWN	FC		06/13/97
	CHECKED			

SITE & DEMOLITION PLAN SHEET OF 2 9

LEGEND

BORING LOCATION AND NUMBER (SEE SPECIAL PROVISION)

263-1100
BLUE STAKE



MATCH LINE SHEET 4

▲ BENCH MARK: BC FLUSH
INTERSECTION SHEA BLVD & 46TH ST.
ELEV. 1390.42

- REMOVE**
- 1 REMOVE CONCRETE CURB & GUTTER, 74 LF.
 - 2 REMOVE CONCRETE SIDEWALK, 170 SF.
 - 3 REMOVE TREE (NPI).

- CONSTRUCT**
- 1 CONSTRUCT NEW DRIVEWAY CITY OF PHOENIX DET P-1255, W=20, 4' WINGS, 280 SF TOTAL.
 - 2 INSTALL 42' CLASS IV RGRCP
 - 3 CONSTRUCT SPECIAL OUTLET STRUCTURE (SEE DETAILS SHT) 1 EA.
 - 4 CONSTRUCT NEW MANHOLE/JUNCTION STRUCTURE (SEE DETAILS SHT) 1 EA.
 - 5 CONSTRUCT CURB & GUTTER, MAG STD DET 220, TYPE 'A', 18 LF TOTAL.
 - 6 REPLACE A.C. PAVEMENT, 34 SY.
 - 7 INSTALL 15" DIP, CL 52, 16 LF

SM SAWCUT & MATCH EXISTING

3			
2			
1			
NO.	REVISION	BY	DATE

FLOOD CONTROL DISTRICT
OF MARICOPA COUNTY
ENGINEERING DIVISION

TATUM WASH DETENTION BASIN

	DESIGNED	MAL	BY	DATE
	DRAWN	FC		06/12/97
	CHECKED			06/12/97


NORTH HALF BASIN GRADING SHEET OF 3 9

363-1100
BLUE STAKE

CURVE DATA:

- ① R = 217.50'
- R = 38.03'
- L = 75.30'
- Δ = 19°50'07"

MATCH LINE SHEET 3




CONSTRUCTION COORDINATE DATA			
St. No.	Description	Northing	Easting
①	STA. 0+00.00	N939025.54	E479466.93
②	PC, STA. 0+70	N939083.66	E479528.99
③	PT, STA. 160+00	N939124.69	E479591.68
④	POT, STA. 2+62.29	N939165.01	E479685.37

REMOVE

○ CONSTRUCT ○

- ① CONSTRUCT SPILLWAY STRUCTURE (SEE DETAIL SHEET)
- ② APPLY SHOTCRETE 6" THICK OVER 6x6-W4xW4.



▲ BENCH MARK: BC FLUSH INTERSECTION SHEA BLVD & 46TH ST. ELEV. 1390.42

NO.	REVISION	BY	DATE
3			
2			
1			


FLOOD CONTROL DISTRICT OF MARICOPA COUNTY ENGINEERING DIVISION

TATUM WASH DETENTION BASIN


	BY	DATE
DESIGNED	MAL	06/13/97
DRAWN	FC	06/13/97
CHECKED		




ALL ASPHALT PAVES SURFACES SHALL BE BLUE STAKE



DETAIL C6-1
SINGLE GATE ELEVATION
NTS





SINGLE GATE CONNECTION TO COLUMN
DETAIL C6-2
SINGLE GATE STOPPER POST CHAIN AND LOCK CONNECTION
NTS



- NOTES:
1. ALL SURFACES TO BE PAINTED PER SPECIAL PROVISIONS. COLOR TO BE DULL BLACK.
 2. HANDRAIL TO BE INSTALLED AT TOWNLEY AVENUE SPILLWAY, DOUBLE 6'X4' CBC OUTLET HEADWALL, AND 48" RGRCP PIPE OUTLET HEADWALL.


STEEL RAILING DETAIL
NTS

3			
2			
1			
NO.	REVISION	BY	DATE
FLOOD CONTROL DISTRICT OF MARICOPA COUNTY ENGINEERING DIVISION			
TATUM WASH DETENTION BASIN			
PRELIMINARY NOT FOR CONSTRUCTION	DESIGNED	MAL	06/12/97
	DRAWN	FC	06/12/97
	CHECKED		
BY			DATE
FENCE DETAIL			SHEET OF 2 9




3			
2			
1			
NO.	REVISION	BY	DATE
FLOOD CONTROL DISTRICT OF MARICOPA COUNTY ENGINEERING DIVISION			
TATUM WASH DETENTION BASIN			
		BY	DATE
	DESIGNED	KVH	06/13/97
	DRAWN	FC	06/13/97
	CHECKED		
DETENTION BASIN CROSS SECTION			SHEET OF 7 9

0+70 1398.30
 1+60.25 1398.25
 2+23.78 1380.5
 2+62 1380.5



①
 R = 217.50'
 T = 38.03'
 L = 75.30'
 Δ = 19°50'07"



3			
2			
1			
NO.	REVISION	BY	DATE
FLOOD CONTROL DISTRICT OF MARICOPA COUNTY ENGINEERING DIVISION			
TATUM WASH DETENTION BASIN			
PRELIMINARY NOT FOR CONSTRUCTION	DESIGNED	MAL	06/02/97
	DRAWN	FC	06/02/97
	CHECKED		
CHUTE BLOCK PLAN			SHEET OF 1 2

Project Charter

We, the team members of the Tatum Wash construction project team agree that we will commit to the below stated goals and work within a framework that says "Partnering."

- Complete project to meet or exceed specifications (quality)
- Harmony
- Open, clear and concise communications
- Complete on time
 - * demobilized (150 days)
 - * Payment 14 days later
- Zero unresolved issues (settle within 14 days)
- Realistic schedule with intent for it to be used
- Profitable to all
- Zero accidents
- A safe and continuous traffic flow
- Sensitivity to the public

W. M. Birch

Shirley
Manning

W. B. Felt

Aaron M. Cross

William Greer

Paul Lee

Timothy L. Cook

Linda Reinhold

Gary Binn
Gary Dine

Lee Berwick

Harvey M. Brown

PARTNERING SESSION
FOR
TATUM WASH
Flood Control District of Maricopa County

FINAL REPORT

Prepared By:

RH & ASSOCIATES
"Partnering Specialists"

4001 E. Bell Road # 114
Phoenix, AZ 85032
(602) 493-1947

2726 Shelter Island Drive #413
San Diego, California 92106
(619) 224-1966

Project # 7820495

PARTNERING SESSION WORKSHOP

**Conducted on
October 21, 1997**

PROJECT PARTNERS

**Buesing Corporation
Flood Control District of Maricopa County
City of Phoenix
Cross Brothers Contracting, Inc.
CMX Constructors, Inc.
Arizona Construction Services**

**Facilitator:
Robin Halperin**

PARTNERING WORKSHOP ATTENDEES
September 23, 1997

		PHONE	FAX
Buesing Corporation 1635 E. University Drive Phoenix, AZ 85034			
Jerry Buesing	President	(602)276-5555	257-9096
Richard Candelaria	Asst. Project Manager	“	257-1778
Dave Reeg	Project Superintendent	“	“
 Flood Control District of Maricopa County 2801 W. Durango Phoenix, AZ 85009			
Heidi Birch	Contract Manager	(602) 506-8126	506-1663
Tim Burkeen	Construction Manager	(602) 506-4178	506-8165
Fred Fuller	Branch Construction Manager	(602) 506-4728	
Tom Johnson	PPM	(602) 506-4703	506-8561
Michael Lopez	Civil Branch Manager	(602) 506-8742	506-4601
Linda Reinbold	Administrative Assistant	(602) 506-8949	506-8165
 City of Phoenix 200 W. Washington - 6th Floor Phoenix, AZ 85003-1611			
John Perez, Jr.	Chief Engineering Tech. (Traffic/COP)	(602) 495-6934	495-0336
 CMX Constructors Inc. 1515 E. Missouri - Ste. 115 Phoenix, AZ 85014			
Jerry Hine	Estimator	(602) 279-8436	279-8498

PARTNERING IS.....

The team defined partnering based on each member's prior experiences.

- Improve quality
 - * Happy Contractors do quality work!
 - * Things done per the specifications are better
 - * When we look at a set of plans or drawings, we see the same thing

- Provides for a "Win-Win" attitude
 - * Mutual respect for each other
 - * "You scratch my back, I'll scratch yours"
 - * When one wins, everybody wins --team effort
 - * No sink or swim mentality

- Shared Responsibility
 - * No finger-pointing
 - * No hidden agendas
 - * Accepting--not shirking--responsibility
 - * The whole is greater than the sum of the parts--although parts are equal

- Reduce claims and litigation
 - * Change in attitude
 - * Work together
 - * "Our project" attitude
 - * Pro-active approach
 - * Teamwork versus adversarial attitudes
 - * Clear expectations (stated up-front)

- Improve lines of communication
 - * No surprises
 - * Keep the public informed
 - * Keep each other informed
 - * Relationships improve communications
 - * Immediate disclosure of problems
 - * Do what you say you will do
 - * Know who is responsible for what
 - * Keep egos out of it

- Common focus and goals
 - * "Our project" emphasis
 - * Same end product in mind
 - * One team, working together
 - * Identify and resolve problems

GOAL SETTING

The team members discussed the overall goals of the project and developed the following list:


- Complete project to meet or exceed specifications (quality)
- Zero accidents
- A safe and continuous traffic flow
- Sensitivity to the public
- Harmony
- Open, clear and concise communications
- Complete on time
 - * demobilized (150 days)
 - * Payment 14 days later
- Zero unresolved issues (settle within 14 days)
- Realistic schedule with intent for it to be used
- Profitable to all

MISSION STATEMENT

We, the team members of the Tatum Wash construction project team agree that we will commit to the above stated goals and work within a framework that says "Partnering."


COMMUNICATION PLANS

FLOOD CONTROL DISTRICT OF MARICOPA COUNTY



COMMUNICATION PLANS (CONT)

BUESING CORPORATION



COMMUNICATION PROCESSES

Inspections

- Tim to be involved everyday - all day
- Advance notification is requested
 - * Placement cards utilized (24 hour notice)
- Anything that requires lab testing
 - * Backfill
 - * Compaction
 - * Asphalt
 - * Concrete placement
- City of Phoenix will be there daily as well to monitor traffic, etc.
- City of Phoenix must be notified prior to doing 15" sewer line

Partnering Follow-up

- There will be two informal follow-up meetings. The time and location will be determined and announced by Tim.

PROJECT ISSUES

1. Traffic Control
 - * City of Phoenix Concerns
 - * Hauling
 - * Route
 - * Holidays
2. Parking
3. Schedule
 - * Work hours
 - * Coordination
 - * Scheduling testers
4. Public Relations
5. Dust & Noise Control
6. N.O.I.'s

ISSUE RESOLUTIONS

Prior to the workshop, several team members provided areas of concern that they wished to discuss during the workshop. Additional issues were identified at the workshop. The following represents those issues and the discussions relating to each one.

1. TRAFFIC CONTROL	
	<ul style="list-style-type: none"> ➤ Traffic control must be legal and safe at all times ➤ Phoenix Police Department can be contracted if there are problems, as long as traffic control efforts are within legal limits
Haul Plan	<ul style="list-style-type: none"> ➤ The haul plan has not been submitted and approved per our understanding at this time ➤ It needs to go to John who will send it through Development Services
	<ul style="list-style-type: none"> ➤ Dave will get the haul plan to Tim and John (COP); if it has already been submitted, Dave will get a copy to them as soon as possible
	<ul style="list-style-type: none"> ➤ During the holidays - non-peak hours for hauling is preferred (8:30-4:30) <ul style="list-style-type: none"> * John is more flexible in the Eastbound lanes than the Westbound lanes
Schedule	<ul style="list-style-type: none"> ➤ Buesing handed out a schedule at this session ➤ Duration of haul is 6/7 weeks (may be altered based on the City of Phoenix needs)
NTP	<ul style="list-style-type: none"> ➤ Notice to proceed expected within one week from today
Message Boards	<ul style="list-style-type: none"> ➤ Variable message boards must be available <ul style="list-style-type: none"> * Need at least one week for public notice * Contractor will try to do this (preferably 2 weeks)
Traffic Load	<ul style="list-style-type: none"> ➤ Reduction in traffic loads will be a "win-win" for all
2. PEDESTRIAN ROUTING	
ADA Requirements	<ul style="list-style-type: none"> ➤ ADA requirements are the concern ➤ Pedestrian routing plan needs to be combined with the traffic plan (proper routing with accessibility (ramps), keeping safety in mind, is the need)

ISSUE RESOLUTIONS (CONT)

<p>ADA Requirements (cont)</p>	<ul style="list-style-type: none"> ➤ Need to look at the signage and comply
<p>3. DETOUR PLAN</p>	
	<ul style="list-style-type: none"> ➤ The plan should be done by a registered traffic engineer rather than a Civil Engineer <ul style="list-style-type: none"> * This is already in the submittal package
	<ul style="list-style-type: none"> ➤ John will look at what has been done up to this point, but really wants a “stamped plan”--will evaluate and advise
<p>4. SIGNAGE</p>	
<p>Temporary</p>	<ul style="list-style-type: none"> ➤ Routing signs need to move or redirect traffic to an alternate route (off of the worksite area) ➤ John will help with verbiage if needed
<p>5. LANE RESTRICTIONS</p>	
	<ul style="list-style-type: none"> ➤ Need to be per the specifications <ul style="list-style-type: none"> * Can drop to one lane on weekends * 2 lanes Westbound utilizing frontage at all times is acceptable * Peak hours congestion is a major concern --safety cannot be compromised
<p>6. TRAFFIC CONTROL SPECIALIST</p>	
	<ul style="list-style-type: none"> ➤ John would prefer someone other than the Contractor ➤ Dave R. is this designated traffic control person. Dave explained how he foresees being able to fulfill this position and not have it interfere with his work as project manager. ➤ John will deal with this through protocol, but when traffic or safety may be compromised, he will go to the appropriate source immediately
<p>7. COURTESY CALLS - TO CITY OF PHOENIX</p>	
	<ul style="list-style-type: none"> ➤ All emergency conditions or anything else going on affecting the City of Phoenix, call 262-6235 dispatcher ➤ “Keep them informed”, it will go on to their database immediately ➤ Tim will be the contact person for this call

ISSUE RESOLUTIONS (CONT)

	<ul style="list-style-type: none"> ➤ John will write all press releases, informing the public <ul style="list-style-type: none"> * This first call needs to be with information regarding the start date of the project (NTP)
	<ul style="list-style-type: none"> ➤ Lead time for changed conditions (Keep it generic) must be noted ➤ Can call John directly
8. NIGHTWORK/NOISE	
	<ul style="list-style-type: none"> ➤ Be aware of night time restrictions--will not limit work but could restrict some of it (noise mitigation/strobe lights)
	<ul style="list-style-type: none"> ➤ At the first weekly meeting the team will take a look at how the work will proceed (include John at this meeting for input)
	<ul style="list-style-type: none"> ➤ After the NTP, Jerry will set up a meeting (John would like to meet at 10:30 a.m.), regarding the noise issues and the night work issues <ul style="list-style-type: none"> * Attendees will be John, Richard, Tim, Jerry, Bill and Dave
9. PARKING	
Mechanics of operation	<ul style="list-style-type: none"> ➤ Parking on the project is OK ➤ Vacant lots seem to be available and this is not anticipated to be a problem
10. CONDUCT	
	<ul style="list-style-type: none"> ➤ Must be a good neighbor at all times ➤ Be sensitive--This is a high profile project with many concerns due to the heavy traffic problem in the area
11. NOTICE OF INTENT	
	<ul style="list-style-type: none"> ➤ There is a Federal requirement if the project is larger than 5 acres <ul style="list-style-type: none"> * This project is smaller than that * Tim is going to check on this requirement and make sure that this team doesn't have to comply ➤ Tim will get with Dave on the control of the discharge <ul style="list-style-type: none"> * The goal is not to cause sediment at the end of the storm drain

CONFLICT MANAGEMENT PLAN

BUESING

FLOOD CONTROL DISTRICT

Level 1

Dave R.	Tim B.
---------	--------

Time: 1 day or TBD

Level 2

Jerry B.	Fred F.
----------	---------

Time:

Level 3

Jerry B.	Tom J.
----------	--------

Time:

RULES OF ESCALATION

- 1) Issues need to be clearly defined by all parties. Deal with pertinent facts, separate the technical issues from policy issues and business issues, maintain the original definition throughout the escalation process.
- 2) Once defined, document what the issue is and give a status review for the next level to consider, and utilize the appropriate form at every level.
- 3) Either party may initiate "escalation", but acknowledgment is required by both parties. Once "escalation" is initiated, the issue should be transmitted jointly by those involved from one level to the next level, to eventual resolution.
- 4) Once an issue is in the process, it should be resolved at the Level closest to the issue.

TEAM MAINTENANCE

The team discussed how it would maintain the Partnering spirit and how it would evaluate its performance relative to the set goals.

Partnering Follow-up

- ➔ The team agreed to look at a *Partnering Rating Summary* which RH & Associates will provide under separate cover for this project. From this summary, the team will verbally discuss the goals and evaluate the project.
- ➔ Two follow-up meetings will held, Tim will find a location and determine the time.

Close Out - RH & Associates recommends a close-out session be scheduled approximately six weeks prior to the end of the project.

➔ **Close Out Questionnaire**

A final questionnaire should be completed. This should include questions pertaining to the team, communications, resources, problems, etc. The team members will also be asked how each perceived the accomplishments of the team in relation to the goals developed for this project.

➔ **Close Out Meeting**

After the questionnaires have been completed and the team Charter rated, a final meeting should be held to discuss the positives of the project; the Partnering process; any negatives or suggestions for future projects. The use of a facilitator at this meeting is not usually required. However, RH is available if needed.

Reward Team Performance - The team talked about the importance of rewarding successful performance. Guidelines for rewarding successful performance include:

- ➔ Reward soon after the accomplishment - don't wait
- ➔ Be specific about what you're rewarding - set milestones to celebrate
- ➔ Be consistent - never take your team members for granted

SUMMARY EVALUATION OF THE PARTNERING RATING FORMS

The evaluation of the workshop provides an opportunity for participants to suggest ways to improve future workshops. Areas evaluated include the quality of the workshop, effectiveness of the facilitators and the process used.

Total Returned Forms =10

Criteria	Poor	Fair	Average	Good	Great
Length of workshop	--	--	50%	40%	10%
Understanding of partnering before workshop	--	10%	--	60%	30%
Understanding of partnering after workshop	--	--	--	30%	70%
Overall program content	--	--	10%	80%	10%
How would you rate the facility	--	--	40%	50%	10%
Did the workshop session meet expectations	--	--	10%	60%	30%
Effectiveness of facilitators presenting partnering	--	--	--	40%	60%
Effectiveness of facilitators with technical issues	--	--	10%	40%	50%
Adequate mix of participants	--	--	20%	50%	30%

EVALUATION COMMENTS BY PARTICIPANTS

What do you consider to be the strongest aspect of this workshop?

- ◆ The efforts put forth by Robin to be precise and on track
- ◆ The facilitator
- ◆ Good up front work
- ◆ All participating vocally
- ◆ Communication
- ◆ Exchange of ideas
- ◆ The cooperation of all those present
- ◆ Getting people together and "communicating" helps a great deal in any situation
- ◆ The facilitator was very direct and concise

PARTNERING WORKSHOP EVALUATION (CONT)

What do you consider to be the weakest aspect of this workshop?

- ◆ Some elements - such as communication techniques/skills skimmed over
- ◆ Not enough participants showed up
- ◆ Location
- ◆ Not everyone showed up that needed to

How can we make the Partnering workshops more effective?

- ◆ I think this was very good
- ◆ Arrange for a facility that has its' own parking
- ◆ Keep up the good work
- ◆ If more time was available for the workshop
- ◆ Could be a little shorter